

STONEFIELD


STORMWATER MANAGEMENT REPORT

**PROPOSED SCHOOL
BLOCK 2104, LOT 21
60 SUNSET ROAD
PEQUANNOCK TOWNSHIP
MORRIS COUNTY, NEW JERSEY**

**PREPARED FOR:
ONE SCHOOL GLOBAL**

**PREPARED BY:
STONEFIELD ENGINEERING & DESIGN, LLC
92 PARK AVENUE
RUTHERFORD, NJ**

**REPORT DATE:
OCTOBER 17, 2022**



**JAKE MODESTOW, PE
NJ PE LICENSE #56119**

I CERTIFY UNDER PENALTY OF LAW THAT I HAVE PERSONALLY EXAMINED AND AM FAMILIAR WITH THE INFORMATION SUBMITTED IN THIS DOCUMENT AND ALL ATTACHMENTS AND THAT, BASED ON MY INQUIRY OF THOSE INDIVIDUALS IMMEDIATELY RESPONSIBLE FOR OBTAINING AND PREPARING THE INFORMATION, I BELIEVE THAT THE INFORMATION IS TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR KNOWINGLY SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT.

REPORT CONTENTS

1.0	PROJECT DESCRIPTION	3
2.0	EXISTING CONDITIONS.....	3
	EXISTING SITE DEVELOPMENT	3
	EXISTING TOPOGRAPHY	3
	PROJECT SITE SOILS.....	4
	WATERSHED / RECEIVING WATERS – TMDL DESIGNATION.....	4
	EXISTING ENVIRONMENTAL INVENTORY.....	4
3.0	PROPOSED CONDITIONS.....	5
	PROPOSED SITE DEVELOPMENT	5
	PROPOSED TOPOGRAPHY	5
	ANTICIPATED ENVIRONMENTAL INVENTORY IMPACTS.....	5
4.0	STORMWATER MANAGEMENT METHODOLOGY & PARAMETERS.....	5
	HYDROLOGIC METHODOLOGY.....	5
5.0	STORMWATER ANALYSIS	6
	EXISTING DRAINAGE AREAS	6
	PROPOSED DRAINAGE AREAS.....	6
	STORMWATER MANAGEMENT DESIGN PARAMETERS	7
	STORMWATER RUNOFF QUANTITY	8
	STORMWATER RUNOFF QUALITY	9
	GROUNDWATER RECHARGE	9
	STORMWATER PIPE CONVEYANCE SYSTEM	9
6.0	STORMWATER FACILITY OPERATIONS & MAINTENANCE	10
7.0	EROSION & SEDIMENT CONTROL.....	10
8.0	CONCLUSIONS	10
9.0	REFERENCES.....	10

APPENDICES

PROJECT FIGURES A

USGS LOCATION MAP..... FIGURE 1

TAX & ZONING MAP FIGURE 2

AERIAL MAP..... FIGURE 3

FEMA MAP..... FIGURE 4

SITE PLAN..... FIGURE 5

PROJECT SOILSB

NRCS SOILS REPORTB-1

HYDROLOGIC & HYDRAULIC CALCULATIONS..... C

HYDROCAD NODE SCHEMATIC DIAGRAMC-1

HYDROCAD HYDROLOGIC CALCULATIONS.....C-2

2-YEAR STORM EVENT HYDROGRAPHS

10-YEAR STORM EVENT HYDROGRAPHS

100-YEAR STORM EVENT HYDROGRAPHS

WATER QUALITY STORM EVENT HYDROGRAPHS

DETENTION BASIN STAGE-STORAGE TABLES

DETENTION BASIN DEWATERING HYDROGRAPH TABLE (100-YEAR EVENT)

DRAINAGE AREA MAPS..... D

EXISTING DRAINAGE AREA MAP 1 OF 2

PROPOSED DRAINAGE AREA MAP2 OF 2

1.0 PROJECT DESCRIPTION

One School Global is proposing to redevelop Block 2104, Lot 21, commonly known as 60 Sunset Road, Pequannock, Morris County, New Jersey (herein referred to as the “project site”) to accommodate a 27,825 SF school. Additional improvements include a soccer field, hard court, onsite parking, lighting, utilities, stormwater management systems and other associated site improvements.

The property is located within the R-15 Residential District of Pequannock Township. The proposed development is bounded by de Wilde Drive to the north, Sunset Road to the south, Roome Avenue to the east, and residential dwellings to the west. The site will be accessed via one (1) ingress-only driveway and one (1) egress-only driveway along Sunset Road. Refer to **APPENDIX A** for project maps of the project site.

The project site is 173,411 SF (3.98 acres), the extent of land disturbance is 178,670 SF (4.10 acres), and the total area of new impervious surfaces is 24,354 SF (0.56 acres). In addition, the project proposes the addition of 10,187 SF (0.23 acres) of new motor vehicle surface. The overall drainage area was modeled as 173,411 SF (3.98 acres).

This Report has been prepared to analyze the potential stormwater runoff impacts of the proposed project site and outline proposed measures to conform to the stormwater management regulations set forth by the Pequannock Township, Morris County Soil Conservation District, Morris County, the New Jersey Administrative Code NJAC), and the New Jersey Department of Environmental Protection (NJDEP).

2.0 EXISTING CONDITIONS

EXISTING SITE DEVELOPMENT

The project site is located along the northerly side of Sunset Road and is bounded by Roome Avenue to the east and de Wilde Drive to the north. The project site has been historically developed with a one-story Pompton Valley Presbyterian Church, one-story Sunset Co-op Nursery School, and a two-story residential dwelling with associated improvements including parking facilities and small accessory structures. The existing development is comprised of 46,746 SF of impervious area. An Aerial Map depicting the existing site conditions can be found in **APPENDIX A**.

EXISTING TOPOGRAPHY

The project site is generally flat. On-site topography slopes generally toward either the south towards the Sunset Road right-of-way, north towards Dewilde Drive, or east towards Roome Avenue, with several low points in the center of the site which ultimately discharge into the Township’s municipal storm drain system.

PROJECT SITE SOILS

Soil mapping was obtained from the National Resource Conservation Service (NRCS) for the project site and immediate area. Generally, the project site is underlain with one (1) major soil group: Urban Land-Riverhead complex (USRHVB). Overall, the soils drain well, and runoff flows overland directly to the municipal storm drain conveyance system. The table below provides a summary of soils for the project site:

TABLE 1: NRCS SOIL MAPPING RESULTS

Soil Unit Code	Soil Description	Approximate Project Coverage	Drainage Class	Hydrologic Soil Group
USRHVB	Urban land-Riverhead complex, 3% to 8% Slopes	100.0%	Well drained	B

Additional information regarding the NRCS soil mapping can be found in **APPENDIX B**.

WATERSHED / RECEIVING WATERS – TMDL DESIGNATION

Under existing conditions, the site drains to the Township of Pequannock storm drain system that ultimately discharges to the Pompton River, State Waterbody ID NJ02030103110020-01. The watershed for the development is part of the Pompton River as defined by the United States Environmental Protection Agency for Community Waterway Mapping. Per the New Jersey 2020 Integrated List of Waters prepared by the New Jersey Department of Environmental Protection, the Pequannock River is identified as impaired water for *Escherichia Coli* and Arsenic.

EXISTING ENVIRONMENTAL INVENTORY

Based on the survey and FEMA flood insurance rate mapping (FEMA Map #3453110003C revised 09/17/1992), the entire site is in Zone X. The majority of the site is located in the Unshaded Zone X which is determined to be outside the 500-year floodplain. The southern portion of the site is located in the Shaded Zone X which includes areas of 500-year flood, areas of 100-year flood with average depths of less than 1 foot or with drainage areas less than 1 square mile, and areas protected by levees from 100-year flood. The FEMA Map can be found in **APPENDIX A** of this Report.

There are no federal (US Army Corps of Engineers) or state (NJDEP) regulated freshwater wetlands within 500 feet of the project site. Impacts to nearby freshwater wetlands are not anticipated with the proposed development. No records of endangered or threatened species sightings/suitable habitats are located within the vicinity of the proposed improvements.

3.0 PROPOSED CONDITIONS

PROPOSED SITE DEVELOPMENT

The proposed development will consist of a 27,825 SF School. Additional improvements include a soccer field, hard court, new site access, parking facilities, utilities, lighting, landscaping, and stormwater management improvements. The site will be accessed via one (1) ingress-only driveway and one (1) egress-only driveway along Sunset Road. Refer to **APPENDIX A** for a half-size Overall Site Plan depicting the proposed project improvements.

PROPOSED TOPOGRAPHY

Project site topography and drainage patterns will generally remain similar to existing conditions; however, as the site is extremely flat in existing conditions, additional fill has been provided on site to ensure positive pitch throughout the development. Additionally, ADA compliant grades (1.0% to 2.0%), have been provided along all accessible parking spaces and pedestrian walkways.

ANTICIPATED ENVIRONMENTAL INVENTORY IMPACTS

The proposed development will not disturb land within environmentally regulated areas (buffer areas, floodplains, sand dunes areas, floodways, and special flood zones). As such, permits for floodplain development and buffer zone disturbances will not be required to be obtained from the NJDEP to perform work for this development. The Township will remain apprised of the NJDEP permitting status as the project moves forward should it be determined to be required.

4.0 STORMWATER MANAGEMENT METHODOLOGY & PARAMETERS

HYDROLOGIC METHODOLOGY

The analysis program “HydroCAD” Version 10.0 by HydroCAD Software Solutions was utilized to calculate and plot the runoff hydrographs. The program incorporates the time of concentration, C values, rainfall data, and project drainage areas to calculate the runoff characteristics. The existing and proposed drainage areas have been analyzed utilizing Intensity-Duration-Frequency data obtained from NOAA for the project area; specifics of the rainfall distribution can be found in **APPENDIX C**. Additional key variables utilized in the analysis include:

TABLE 2: HYDROCAD DESIGN VARIABLES

Variable	Input	Variable	Input
Runoff Calculation Method	SCS TR-20	NRCS Rainfall Frequency Data Set	Morris
Pervious/Impervious CN Calculations	Separate	Storm Intervals (Year Events)	2, 10, 100
Stage-Storage Relationship	Dynamic	Storm Duration	24 Hours
Minimum time of concentration	6 minutes	Storm Curve	NOAA D

Additional information regarding the hydrologic calculations can be found in **APPENDIX C**.

5.0 STORMWATER ANALYSIS

EXISTING DRAINAGE AREAS

Under current conditions, the project site is subdivided into three (3) drainage areas, ultimately outfalling to three (3) Points of Interest (POI). Drainage area EX-1 consists of the center and western portion of the site including two (2) buildings and a parking lot, ultimately draining towards the Sunset Road right-of-way (POI-1). Area EX-2 consists of the eastern portion of the site including one building, ultimately draining towards the Roome Avenue (POI 2). Area EX-3 consists of the northwest portion of the site including the playground area and shed, ultimately draining towards Dewilde Drive (POI 3). See below for a short summary of each area:

TABLE 4: SUMMARY OF EXISTING DRAINAGE AREAS

Drainage Area	Description	Area Extents	Impervious Area	Time of Concentration
EX-1	Existing Drainage to Sunset Road Right-of-Way	87,431 SF	30,985 SF	11.8 Minutes
EX-2	Existing Drainage to Roome Avenue Right-of-Way	59,447 SF	13,506 SF	5.1 Minutes
EX-3	Existing Drainage to Dewilde Drive Right-of-Way	26,533 SF	255 SF	16.6 Minutes

All existing drainage areas were delineated based on field surveying data. Hydrologic calculations and parameters for each drainage area can be found in **APPENDIX C**; specific drainage area delineations and land cover can be found in **APPENDIX E**.

PROPOSED DRAINAGE AREAS

Under proposed conditions the site is comprised of six (6) drainage areas with three (3) Points of Interest (POI). Drainage area P-1A drains to Basin B-1, an infiltration basin along Sunset Road. Drainage area P-1B drains into a porous paving system in the tandem parking stalls, Basin B-2. Drainage area P-1C drains to Basin B-3, an infiltration basin in the rear of the site. Drainage area P-1D sheet flows undetained towards POI 1. Drainage area P-2 flows undetained to POI-2. Drainage area P-3 flows undetained toward POI-3. See below for a short summary of each area:




TABLE 5: SUMMARY OF PROPOSED DRAINAGE AREAS

Drainage Area	Description	Area Extents	Impervious Area	Time of Concentration
P-1A	Proposed Drainage to Infiltration Basin Along Sunset Road	54,424 SF	42,912 SF	2.1 Minutes
P-1B	Proposed Drainage to Porous Pavement in Tandem Spaces	13,171 SF	13,039 SF	2.6 Minutes
P-1C	Proposed Drainage to Infiltration Basin in Rear	52,620 SF	7,880 SF	10.1 Minutes
P-1D	Undetained Flow to Sunset Road	13,843 SF	1,805 SF	9.3 Minutes
POI-1	Proposed Drainage to Sunset Road	134,058 SF	65,636 SF	--
P-2 (POI-2)	Proposed Drainage to Roome Avenue	36,979 SF	3,464 SF	7.6 Minutes
P-3 (POI-3)	Proposed Drainage to Dewilde Drive	2,374 SF	0 SF	2.7 Minutes

All proposed drainage areas were delineated based on the proposed grading design overlain on field survey data. Hydrologic calculations and parameters for each drainage area can be found in **APPENDIX C**; specific drainage area delineations and land cover can be found in **APPENDIX D**.

STORMWATER MANAGEMENT DESIGN PARAMETERS

The extent of development proposes to disturb more than one acre of land and add more than one-quarter acre of new impervious surfaces. As such, the project is considered a Major Development as defined in the Pequannock Ordinance and NJAC 7:8-1.2. A Major Development is subject to stormwater quantity, quality, and groundwater recharge requirements. See below for a summary of each design parameter and compliance requirements:

TABLE 6: STORMWATER MANAGEMENT DESIGN TARGET SUMMARY TABLE

Design Parameter	Design Target for Compliance
Stormwater Runoff Quantity	Design stormwater management measures so that the post-construction peak runoff rates for the 2-, 10-, and 100-year storm events are 50, 75 and 80 percent, respectively, of the pre-construction peak runoff rates. The percentages apply only to the post-construction stormwater runoff that is attributable to the portion of the site on which the proposed development or project is to be constructed. Demonstrate through hydrologic and hydraulic analysis that for stormwater leaving the site, post-construction runoff hydrographs for the 2-, 10-, and 100-year storm events do not exceed, at any point in time, the pre-construction runoff hydrographs for the same storm events.
Stormwater Runoff Quality	Stormwater management measures shall be designed to reduce the post-construction load of total suspended solids (TSS) in stormwater runoff generated from the water quality storm by 80% of the anticipated load from the developed site, expressed as an annual average.
Groundwater Recharge	The project is exempt from groundwater recharge requirements as the project site is located within State Planning Area PA-1 (Metropolitan).

STORMWATER RUNOFF QUANTITY

To attenuate peak stormwater runoff rates to the mandated regulatory levels two (2) infiltration basins and one (1) porous pavement system with associated outlet control structures are proposed. To analyze runoff quantities between the existing and proposed drainage areas, three (3) points of interest were selected:

TABLE 7: QUANTITY COMPARISON POINTS OF INTEREST

Point of Interest	Area Description	Existing Tributary Drainage Areas	Proposed Tributary Drainage Areas
POI - 1	Drainage to Sunset Road	EX-1	P-1A, P-1B, P-1C, P-1D
POI - 2	Drainage to Roome Avenue	EX-2	P-2
POI - 3	Drainage to Dewilde Drive	EX-3	P-3

The following tables summarize the results for the 2-year, 10-year, and 100-year storm events for each project point of interest:

TABLE 8: PEAK DISCHARGE TO SUNSET ROAD (POI-1)

Rainfall Event	Existing Flow Rate	Required % Reduction	Proposed Flow Rate	Proposed % Reduction
2-Year Storm	2.48 CFS	50%	0.54 CFS	78.23%
10-Year Storm	4.64 CFS	25%	1.69 CFS	63.58%
100-Year Storm	9.18 CFS	20%	7.32 CFS	20.26%

TABLE 9: PEAK DISCHARGE TO ROOME AVENUE (POI-2)

Rainfall Event	Existing Flow Rate	Required % Reduction	Proposed Flow Rate	Proposed % Reduction
2-Year Storm	1.68 CFS	50%	1.09 CFS	35.12%*
10-Year Storm	3.47 CFS	25%	2.25 CFS	35.16%*
100-Year Storm	7.33 CFS	20%	4.64 CFS	36.70%*

*Post-Construction runoff hydrograph does not exceed, at any point in time, the pre-construction runoff hydrograph for the same storm. See **APPENDIX C**.

TABLE 10: PEAK DISCHARGE TO DEWILDE DRIVE (POI-3)

Rainfall Event	Existing Flow Rate	Required % Reduction	Proposed Flow Rate	Proposed % Reduction
2-Year Storm	0.31 CFS	50%	0.09 CFS	70.97%
10-Year Storm	0.85 CFS	25%	0.18 CFS	78.82%
100-Year Storm	2.05 CFS	20%	0.36 CFS	82.44%

*Post-Construction runoff hydrograph does not exceed, at any point in time, the pre-construction runoff hydrograph for the same storm. See **APPENDIX C**.

The proposed infiltration basins and porous pavers provide sufficient flow rate attenuation to ensure that no adverse impacts are anticipated downstream of the project site. Detailed hydrologic calculations for each drainage area can be found in **APPENDIX C**.

STORMWATER RUNOFF QUALITY

The porous pavement system and infiltration basins proposed on site meet the total suspended solids removal (TSS) removal requirements as certified by the NJDEP BMP Manual. The proposed treatment design will exceed the regulatory requirements for stormwater runoff quality and ensure that runoff discharged into the unnamed tributary will not have any adverse effects on downstream waterways and environs.

Stormwater BMP Facility	NJDEP Certified Removal Efficiency
Infiltration Basin (B-1)	80%
Porous Pavement (B-2)	80%
Infiltration Basin (B-3)	80%

GROUNDWATER RECHARGE

As indicated by N.J.A.C. 7:8-5.1, a major development must comply with groundwater recharge requirements. This requirement is waived if the proposed development is located within the Metropolitan Planning Area, also known as the Urban Land Redevelopment Area (PA-1). The site is located within the designated planning area, and as such, is exempt from groundwater recharge requirements.

STORMWATER PIPE CONVEYANCE SYSTEM

The on-site stormwater conveyance system has been sized for the 25-year storm event and is able to safely convey runoff to the proposed stormwater management facilities without overflow or bypass.

6.0 STORMWATER FACILITY OPERATIONS & MAINTENANCE

A Stormwater Operations & Maintenance Manual will be submitted for review to the Township and will be forwarded to the relevant jurisdictional agencies prior to obtaining final land use approvals and permits. Any necessary easements or covenants associated with the stormwater improvements will be recorded prior to the start of construction.

7.0 EROSION & SEDIMENT CONTROL

A Soil Erosion & Sediment Control Plan has been prepared in accordance with the latest edition of the Standards for Soil Erosion and Sediment Control in New Jersey. This plan can be found within the Preliminary & Final Major Site Plans prepared by Stonefield in conjunction with this Report. Proposed temporary measures during construction include silt fencing, stabilized construction entrances, and inlet filters. No land disturbance will occur until certification and permits have been obtained from the Morris County Soil Conservation District.

8.0 CONCLUSIONS

As demonstrated in this Report, the increase in runoff flow rate generated by the proposed development will be satisfactorily mitigated by the introduction of two (2) infiltration basins and one (1) porous pavement system. Runoff water quality will be impacted by the increase in impervious surfaces and motor vehicle surfaces and the proposed infiltration basins and porous pavement system will provide treatment to remove total suspended solids to a satisfactory regulatory level.

The proposed project complies with all applicable stormwater management regulations and standards. As such, the project is not anticipated to have any adverse drainage impacts on neighboring properties, downstream watercourses, or adjoining conveyance systems.

9.0 REFERENCES

1. New Jersey Administrative Code Title 7, Chapter 8 Stormwater Management, last amended March 2, 2020
https://www.nj.gov/dep/rules/rules/njac7_8.pdf
2. New Jersey Stormwater Best Management Practices Manual, last revised March 2, 2020
https://www.njstormwater.org/bmp_manual2.htm
3. Pequannock Township Zoning Code, last amended November 23, 2021
<https://ecode360.com/36915264>

APPENDIX A

PROJECT FIGURES

INVENTORY


FIGURE 1: USGS LOCATION MAP

FIGURE 2: AERIAL MAP

FIGURE 3: TAX & ZONING MAP

FIGURE 4: FEMA MAP


FIGURE 5: SITE PLAN



Z:\Rutherford\RUT-2022\BUT-220209 One School Global - 40 Sunset Road - Pequanock NJ\CADD\Exhibits\Project Map\2022-07-14 Project Map.dwg



AERIAL MAP



SOURCE: GOOGLE EARTH PRO 2020, IMAGE RETRIEVED JULY 11, 2022

ONE SCHOOL GLOBAL PROPOSED SCHOOLING REDEVELOPMENT

BLOCK 2103, LOT 21
60 SUNSET ROAD
TOWNSHIP OF PEQUANNOCK, MORRIS COUNTY, NEW JERSEY


DRAWN BY:	LJ
CHECKED BY:	KB
DATE:	07/14/2022
SCALE:	1" = 200'
PROJECT ID:	RUT-220209

 **STONEFIELD**
engineering & design

Rutherford, NJ • New York, NY • Boston, MA
Princeton, NJ • Tampa, FL • Detroit, MI
www.stonefieldeng.com

Headquarters: 92 Park Avenue, Rutherford, NJ 07070
Phone 201.340.4468 • Fax 201.340.4472

Z:\Rutherford\RUT-2020\2020-2020-09 One School Global - 40 Sunset Road - Pequanock NJ\CADD\Exhibits\Project Map\2022-07-14, Project Maps.dwg



TAX & ZONING MAP

ZONE R-15

ZONE R-11


200' 0' 200' 400'

GRAPHIC SCALE IN FEET


1" = 200'

SOURCE: TOWNSHIP OF PEQUANNOCK TAX MAP SHEETS 21 & 25 DATED APRIL 28, 2005. TOWNSHIP OF PEQUANNOCK ZONING MAP DATED APRIL, 2021. ONE SCHOOL GLOBAL PROPOSED SCHOOLING REDEVELOPMENT BLOCK 2103, LOT 21 60 SUNSET ROAD TOWNSHIP OF PEQUANNOCK, MORRIS COUNTY, NEW JERSEY	DRAWN BY: UJ	STONEFIELD engineering & design Rutherford, NJ · New York, NY · Boston, MA Princeton, NJ · Tampa, FL · Detroit, MI www.stonefieldeng.com Headquarters: 92 Park Avenue, Rutherford, NJ 07070 Phone 201.340.4468 · Fax 201.340.4472
	CHECKED BY: KB	
	DATE: 07/14/2022	
	SCALE: 1" = 200'	
	PROJECT ID: RUT-220209	

Z:\Rutherford\RTUT-2022\RTUT-202209 One School Global - 40 Sunset Road - Pequanock NJ\CADD\Exhibits\Project Map\2022-07-14 Project Map.dwg



EFFECTIVE FEMA FIRM MAP



SOURCE: FLOOD INSURANCE RATE MAP, MORRIS COUNTY, NEW JERSEY, MAP NUMBERS 3453110003C DATED SEPTEMBER 17, 1992.

ONE SCHOOL GLOBAL PROPOSED SCHOOLING REDEVELOPMENT


BLOCK 2103, LOT 21
60 SUNSET ROAD
TOWNSHIP OF PEQUANNOCK, MORRIS COUNTY, NEW JERSEY

DRAWN BY:	UJ
CHECKED BY:	KB
DATE:	07/14/2022
SCALE:	1" = 1000'
PROJECT ID:	RTUT-220209

**STONEFIELD**
engineering & design

Rutherford, NJ · New York, NY · Boston, MA
Princeton, NJ · Tampa, FL · Detroit, MI
www.stonefieldeng.com

Headquarters: 92 Park Avenue, Rutherford, NJ 07070
Phone 201.340.4468 · Fax 201.340.4472



USGS QUADRANGLE MAP

1000' 0' 1000' 2000'



GRAPHIC SCALE IN FEET

1" = 1000'

SOURCE: UNITED STATES GEOLOGICAL SURVEY QUADRANGLE MAP, POMPTON PLAINS, NEW JERSEY, 7.5 MINUTE SERIES, 2019.

ONE SCHOOL GLOBAL PROPOSED SCHOOLING REDEVELOPMENT

BLOCK 2103, LOT 21
60 SUNSET ROAD
TOWNSHIP OF PEQUANNOCK, MORRIS COUNTY, NEW JERSEY

DRAWN BY:

UJ

CHECKED BY:

KB

DATE:

07/14/2022

SCALE:

1" = 1000'

PROJECT ID:

RUT-220209




STONEFIELD
engineering & design

Rutherford, NJ · New York, NY · Boston, MA
Princeton, NJ · Tampa, FL · Detroit, MI
www.stonefieldeng.com

Headquarters: 92 Park Avenue, Rutherford, NJ 07070
Phone 201.340.4468 · Fax 201.340.4472

APPENDIX B

PROJECT SOILS





United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for **Morris County, New Jersey**



August 8, 2022

Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.


Contents

Preface	2
Soil Map	5
Soil Map.....	6
Legend.....	7
Map Unit Legend.....	8
Map Unit Descriptions.....	8
Morris County, New Jersey.....	10
USRHVB—Urban land-Riverhead complex, 3 to 8 percent slopes.....	10
References	12


Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



Map Scale: 1:1,330 if printed on A landscape (11" x 8.5") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 18N WGS84

Custom Soil Resource Report

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features

 Blowout

 Borrow Pit

 Clay Spot

 Closed Depression

 Gravel Pit

 Gravelly Spot

 Landfill

 Lava Flow

 Marsh or swamp

 Mine or Quarry

 Miscellaneous Water

 Perennial Water

 Rock Outcrop

 Saline Spot

 Sandy Spot

 Severely Eroded Spot

 Sinkhole

 Slide or Slip

 Sodic Spot

 Spoil Area

 Stony Spot

 Very Stony Spot

 Wet Spot

 Other

 Special Line Features

Water Features

 Streams and Canals

Transportation

 Rails

 Interstate Highways

 US Routes

 Major Roads

 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Morris County, New Jersey
Survey Area Data: Version 16, Aug 31, 2021

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Dec 31, 2009—Feb 26, 2017

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
USRHVB	Urban land-Riverhead complex, 3 to 8 percent slopes	7.8	100.0%
Totals for Area of Interest		7.8	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Custom Soil Resource Report

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Morris County, New Jersey

USRHVB—Urban land-Riverhead complex, 3 to 8 percent slopes

Map Unit Setting

National map unit symbol: 13q0d
Elevation: 0 to 950 feet
Mean annual precipitation: 30 to 64 inches
Mean annual air temperature: 46 to 79 degrees F
Frost-free period: 131 to 178 days
Farmland classification: Not prime farmland

Map Unit Composition

Urban land: 60 percent
Riverhead and similar soils: 40 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Urban Land

Setting

Landform: Outwash fans
Landform position (three-dimensional): Base slope, tread
Down-slope shape: Linear, concave
Across-slope shape: Linear
Parent material: Surface covered by pavement, concrete, buildings, and other structures underlain by disturbed and natural soil material

Typical profile

C - 0 to 60 inches: variable

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 8s
Hydric soil rating: Unranked

Description of Riverhead

Setting

Landform: Outwash fans
Landform position (three-dimensional): Base slope
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Glaciofluvial deposits derived from granite and gneiss

Typical profile

A - 0 to 10 inches: sandy loam
Bw - 10 to 26 inches: gravelly sandy loam
BC - 26 to 36 inches: gravelly sandy loam
C - 36 to 60 inches: gravelly sand

Properties and qualities

Slope: 3 to 8 percent
Depth to restrictive feature: More than 80 inches
Drainage class: Well drained
Runoff class: Low

Custom Soil Resource Report

Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: Low (about 5.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 2s

Hydrologic Soil Group: B

Hydric soil rating: No

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf


APPENDIX C

HYDROLOGIC & HYDRAULIC CALCULATIONS

INVENTORY

C-1: HYDROCAD NODE SCHEMATIC DIAGRAM

C-2: HYDROCAD HYDROLOGIC CALCULATIONS





EX-1
Existing Drainage
towards Sunset Road



EX-2
Existing Drainage
towards Roome
Avenue



EX-3
Existing Drainage
towards Dewilde Drive



P-1A
Drainage to Infiltration
Basin Along Sunset
Road



P-1B
Drainage to Porous
Pavement in Tandem
Spaces



P-1C
Drainage to Infiltration
Basin in Rear



P-2
Proposed Drainage to
Roome Avenue



P-3
Proposed Drainage
toward Dewilde Drive



B-1
Infiltration Basin Along
Sunset Road



B-2
Porous Pavement
Within Tandem Spaces




B-3
Infiltration Basin Along
Sunset Road



P-1D
Undetained Flow to
Sunset Road




POI-1
Proposed Drainage to
Sunset Road



Subcat



Reach



Pond



Link

Routing Diagram for 2022-09-21_HydroCAD

Prepared by Stonefield Engineering & Design, Printed 9/30/2022
HydroCAD® 10.20-2f s/n 10626 © 2022 HydroCAD Software Solutions LLC

Area Listing (all nodes)

Area (sq-ft)	CN	Description (subcatchment-numbers)
196,767	61	>75% Grass cover, Good, HSG B (EX-1, EX-2, EX-3, P-1A, P-1B, P-1C, P-1D, P-2, P-3)
2,009	96	Gravel surface, HSG B (EX-3)
44,746	98	Impervious (EX-1, EX-2, EX-3)
37,711	98	Impervious Area (P-1A, P-1B, P-1C, P-1D, P-2)
3,564	98	Porous Pavement (P-1B)
27,825	98	Roof Area (P-1A)
34,200	80	Turf Field (P-1C, P-2, P-3)
346,822	75	TOTAL AREA

Summary for Subcatchment EX-1: Existing Drainage towards Sunset Road

Runoff = 2.48 cfs @ 12.20 hrs, Volume= 11,316 cf, Depth= 1.55"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

	Area (sf)	CN	Description
*	30,985	98	Impervious
	56,446	61	>75% Grass cover, Good, HSG B
	87,431	74	Weighted Average
	56,446	61	64.56% Pervious Area
	30,985	98	35.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.4	100	0.0258	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
1.6	86	0.0031	0.90		Shallow Concentrated Flow, 86 LF SCF (2-3) Unpaved Kv= 16.1 fps
0.1	10	0.0200	2.87		Shallow Concentrated Flow, 10 LF SCF (3-4) Paved Kv= 20.3 fps
1.7	151	0.0080	1.44		Shallow Concentrated Flow, 151 LF SCF (4-5) Unpaved Kv= 16.1 fps
11.8	347	Total			

Subcatchment EX-1: Existing Drainage towards Sunset Road

Hydrograph




Summary for Subcatchment EX-2: Existing Drainage towards Roome Avenue

Runoff = 1.68 cfs @ 12.13 hrs, Volume= 5,983 cf, Depth= 1.21"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

	Area (sf)	CN	Description
*	13,506	98	Impervious
	45,941	61	>75% Grass cover, Good, HSG B
	59,447	69	Weighted Average
	45,941	61	77.28% Pervious Area
	13,506	98	22.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.8	30	0.0170	0.13		Sheet Flow, 30 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	9	0.0110	2.13		Shallow Concentrated Flow, 9 LF SCF (2-3) Paved Kv= 20.3 fps
0.6	39	0.0050	1.14		Shallow Concentrated Flow, 39 LF SCF (3-4) Unpaved Kv= 16.1 fps
0.2	25	0.0092	1.95		Shallow Concentrated Flow, 25 LF SCF (4-5) Paved Kv= 20.3 fps
0.4	31	0.0081	1.45		Shallow Concentrated Flow, 31 LF SCF (5-6) Unpaved Kv= 16.1 fps
5.1	134	Total			

Subcatchment EX-2: Existing Drainage towards Roome Avenue

Summary for Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Runoff = 0.31 cfs @ 12.27 hrs, Volume= 1,659 cf, Depth= 0.75"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

Area (sf)	CN	Description
* 255	98	Impervious
2,009	96	Gravel surface, HSG B
24,269	61	>75% Grass cover, Good, HSG B
26,533	64	Weighted Average
26,278	64	99.04% Pervious Area
255	98	0.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	100	0.0053	0.11		Sheet Flow, 100 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.8	77	0.0111	1.70		Shallow Concentrated Flow, 77 LF SCF (2-3)
					Unpaved Kv= 16.1 fps
16.6	177	Total			

Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Hydrograph




Summary for Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Runoff = 3.81 cfs @ 12.10 hrs, Volume= 12,390 cf, Depth= 2.73"
 Routed to Pond B-1 : Infiltration Basin Along Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 NOAA 24-hr D 2-Year Rainfall=3.54"

	Area (sf)	CN	Description
	11,512	61	>75% Grass cover, Good, HSG B
*	27,825	98	Roof Area
*	15,087	98	Impervious Area
	54,424	90	Weighted Average
	11,512	61	21.15% Pervious Area
	42,912	98	78.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.0	12	0.0127	0.10		Sheet Flow, 12 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	23	0.0167	2.62		Shallow Concentrated Flow, 23 LF SCF (2-3) Paved Kv= 20.3 fps
0.0	21	0.2500	8.05		Shallow Concentrated Flow, 21 LF SCF (3-4) Unpaved Kv= 16.1 fps
2.1	56	Total			

Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Summary for Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Runoff = 1.10 cfs @ 12.10 hrs, Volume= 3,599 cf, Depth= 3.28"

Routed to Pond B-2 : Porous Pavement Within Tandem Spaces


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

Area (sf)	CN	Description
132	61	>75% Grass cover, Good, HSG B
* 3,564	98	Porous Pavement
* 9,475	98	Impervious Area
13,171	98	Weighted Average
132	61	1.00% Pervious Area
13,039	98	99.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	15	0.0127	0.10		Sheet Flow, 15 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.2	41	0.0250	3.21		Shallow Concentrated Flow, 41 LF SCF (2-3)
					Paved Kv= 20.3 fps
2.6	56	Total			

Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Hydrograph



Summary for Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Runoff = 1.40 cfs @ 12.18 hrs, Volume= 5,618 cf, Depth= 1.28"

Routed to Pond B-3 : Infiltration Basin Along Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

Area (sf)	CN	Description
27,952	61	>75% Grass cover, Good, HSG B
* 7,880	98	Impervious Area
* 16,788	80	Turf Field
52,620	73	Weighted Average
44,740	68	85.02% Pervious Area
7,880	98	14.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	100	0.0175	0.17		Sheet Flow, 100 LF Sheet Flow Grass: Short n= 0.150 P2= 3.54"
0.3	33	0.0175	2.13		Shallow Concentrated Flow, 33 LF SCF (2-3) Unpaved Kv= 16.1 fps
10.1	133	Total			

Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Hydrograph



Summary for Subcatchment P-1D: Undetained Flow to Sunset Road

Runoff = 0.25 cfs @ 12.18 hrs, Volume= 1,090 cf, Depth= 0.94"

Routed to Link POI-1 : Proposed Drainage to Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

Area (sf)	CN	Description
12,038	61	>75% Grass cover, Good, HSG B
* 1,805	98	Impervious Area
13,843	66	Weighted Average
12,038	61	86.96% Pervious Area
1,805	98	13.04% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.5	100	0.0250	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	87	0.0135	1.87		Shallow Concentrated Flow, 87 LF SCF (2-3) Unpaved Kv= 16.1 fps
9.3	187	Total			

Subcatchment P-1D: Undetained Flow to Sunset Road

Hydrograph



Summary for Subcatchment P-2: Proposed Drainage to Roome Avenue

Runoff = 1.09 cfs @ 12.15 hrs, Volume= 3,839 cf, Depth= 1.25"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

	Area (sf)	CN	Description
	17,643	61	>75% Grass cover, Good, HSG B
*	3,464	98	Impervious Area
*	15,872	80	Turf Field
	36,979	73	Weighted Average
	33,515	70	90.63% Pervious Area
	3,464	98	9.37% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.6	92	0.0285	0.20		Sheet Flow, 92 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"

Subcatchment P-2: Proposed Drainage to Roome Avenue

Hydrograph



Summary for Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Runoff = 0.09 cfs @ 12.11 hrs, Volume= 239 cf, Depth= 1.21"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 2-Year Rainfall=3.54"

Area (sf)	CN	Description
834	61	>75% Grass cover, Good, HSG B
* 1,540	80	Turf Field
2,374	73	Weighted Average
2,374	73	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.7	16	0.0115	0.10		Sheet Flow, 14 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.0	5	0.0115	1.73		Shallow Concentrated Flow, 5 LF SCF (2-3)
					Unpaved Kv= 16.1 fps
2.7	21	Total			

Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Hydrograph



Summary for Pond B-1: Infiltration Basin Along Sunset Road

Inflow Area = 54,424 sf, 78.85% Impervious, Inflow Depth = 2.73" for 2-Year event
 Inflow = 3.81 cfs @ 12.10 hrs, Volume= 12,390 cf
 Outflow = 0.20 cfs @ 13.75 hrs, Volume= 12,390 cf, Atten= 95%, Lag= 99.3 min
 Discarded = 0.08 cfs @ 13.75 hrs, Volume= 8,698 cf
 Primary = 0.12 cfs @ 13.75 hrs, Volume= 3,692 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.46' @ 13.75 hrs Surf.Area= 6,035 sf Storage= 6,865 cf


Plug-Flow detention time= 543.8 min calculated for 12,389 cf (100% of inflow)
 Center-of-Mass det. time= 543.9 min (1,303.8 - 760.0)

Volume	Invert	Avail.Storage	Storage Description		
#1	187.00'	14,171 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
187.00	3,406	592.8	0	0	3,406
188.00	5,212	611.7	4,277	4,277	5,315
189.00	7,076	630.5	6,120	10,397	7,275
189.50	8,029	639.9	3,774	14,171	8,276

Device	Routing	Invert	Outlet Devices
#1	Primary	186.50'	12.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 186.50' / 185.75' S= 0.0250 ' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.85'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.50'	12.0" W x 2.5" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.15'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	187.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.08 cfs @ 13.75 hrs HW=188.46' (Free Discharge)
 ↳ **5=Exfiltration** (Controls 0.08 cfs)

Primary OutFlow Max=0.12 cfs @ 13.75 hrs HW=188.46' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.12 cfs of 4.57 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.12 cfs @ 3.43 fps)
 ↳ **3=Orifice/Grate** (Controls 0.00 cfs)
 ↳ **4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-1: Infiltration Basin Along Sunset Road

Summary for Pond B-2: Porous Pavement Within Tandem Spaces

Inflow Area = 13,171 sf, 99.00% Impervious, Inflow Depth = 3.28" for 2-Year event
 Inflow = 1.10 cfs @ 12.10 hrs, Volume= 3,599 cf
 Outflow = 0.13 cfs @ 12.73 hrs, Volume= 3,599 cf, Atten= 88%, Lag= 37.8 min
 Discarded = 0.05 cfs @ 12.73 hrs, Volume= 2,913 cf
 Primary = 0.08 cfs @ 12.73 hrs, Volume= 686 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 187.80' @ 12.73 hrs Surf.Area= 3,564 sf Storage= 1,361 cf

Plug-Flow detention time= 159.9 min calculated for 3,599 cf (100% of inflow)
 Center-of-Mass det. time= 159.8 min (913.1 - 753.2)


Volume	Invert	Avail.Storage	Storage Description
#1	186.85'	2,851 cf	Custom Stage Data (Irregular) Listed below (Recalc) 7,128 cf Overall x 40.0% Voids

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
186.85	3,564	306.0	0	0	3,564
187.85	3,564	306.0	3,564	3,564	3,870
188.85	3,564	306.0	3,564	7,128	4,176

Device	Routing	Invert	Outlet Devices
#1	Primary	186.85'	12.0" Round Culvert L= 135.0' Ke= 0.500 Inlet / Outlet Invert= 186.85' / 185.75' S= 0.0081 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.45'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.35'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#4	Discarded	186.85'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 12.73 hrs HW=187.80' (Free Discharge)
 ↳ **4=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=0.08 cfs @ 12.73 hrs HW=187.80' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.08 cfs of 2.54 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.08 cfs @ 2.41 fps)
 ↳ **3=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-2: Porous Pavement Within Tandem Spaces

Summary for Pond B-3: Infiltration Basin Along Sunset Road

Inflow Area = 52,620 sf, 14.98% Impervious, Inflow Depth = 1.28" for 2-Year event
 Inflow = 1.40 cfs @ 12.18 hrs, Volume= 5,618 cf
 Outflow = 0.32 cfs @ 12.70 hrs, Volume= 5,618 cf, Atten= 77%, Lag= 31.0 min
 Discarded = 0.04 cfs @ 12.70 hrs, Volume= 2,820 cf
 Primary = 0.28 cfs @ 12.70 hrs, Volume= 2,798 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.59' @ 12.70 hrs Surf.Area= 3,219 sf Storage= 1,745 cf

Plug-Flow detention time= 155.6 min calculated for 5,618 cf (100% of inflow)
 Center-of-Mass det. time= 155.5 min (997.3 - 841.7)

Volume	Invert	Avail.Storage	Storage Description		
#1	188.00'	7,255 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
188.00	2,670	308.6	0	0	2,670
189.00	3,625	227.5	3,135	3,135	6,140
190.00	4,635	346.3	4,120	7,255	11,572


Device	Routing	Invert	Outlet Devices
#1	Primary	187.50'	12.0" Round Culvert L= 325.0' Ke= 0.500 Inlet / Outlet Invert= 187.50' / 185.85' S= 0.0051 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	188.25'	6.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.80'	3.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.60'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	188.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.10' Phase-In= 0.01'

Discarded OutFlow Max=0.04 cfs @ 12.70 hrs HW=188.59' (Free Discharge)

↑**5=Exfiltration** (Controls 0.04 cfs)

Primary OutFlow Max=0.28 cfs @ 12.70 hrs HW=188.59' TW=0.00' (Dynamic Tailwater)


↑**1=Culvert** (Passes 0.28 cfs of 2.51 cfs potential flow)
 ↑**2=Orifice/Grate** (Orifice Controls 0.28 cfs @ 2.22 fps)
 ↑**3=Orifice/Grate** (Controls 0.00 cfs)
 ↑**4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-3: Infiltration Basin Along Sunset Road

Summary for Link POI-1: Proposed Drainage to Sunset Road

Inflow Area = 134,058 sf, 48.96% Impervious, Inflow Depth = 0.74" for 2-Year event
Inflow = 0.54 cfs @ 12.56 hrs, Volume= 8,267 cf
Primary = 0.54 cfs @ 12.56 hrs, Volume= 8,267 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link POI-1: Proposed Drainage to Sunset Road

Summary for Subcatchment EX-1: Existing Drainage towards Sunset Road

Runoff = 4.64 cfs @ 12.20 hrs, Volume= 20,046 cf, Depth= 2.75"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

	Area (sf)	CN	Description
*	30,985	98	Impervious
	56,446	61	>75% Grass cover, Good, HSG B
	87,431	74	Weighted Average
	56,446	61	64.56% Pervious Area
	30,985	98	35.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.4	100	0.0258	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
1.6	86	0.0031	0.90		Shallow Concentrated Flow, 86 LF SCF (2-3) Unpaved Kv= 16.1 fps
0.1	10	0.0200	2.87		Shallow Concentrated Flow, 10 LF SCF (3-4) Paved Kv= 20.3 fps
1.7	151	0.0080	1.44		Shallow Concentrated Flow, 151 LF SCF (4-5) Unpaved Kv= 16.1 fps
11.8	347	Total			

Subcatchment EX-1: Existing Drainage towards Sunset Road

Hydrograph




Summary for Subcatchment EX-2: Existing Drainage towards Roome Avenue

Runoff = 3.47 cfs @ 12.13 hrs, Volume= 11,432 cf, Depth= 2.31"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

	Area (sf)	CN	Description
*	13,506	98	Impervious
	45,941	61	>75% Grass cover, Good, HSG B
	59,447	69	Weighted Average
	45,941	61	77.28% Pervious Area
	13,506	98	22.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.8	30	0.0170	0.13		Sheet Flow, 30 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	9	0.0110	2.13		Shallow Concentrated Flow, 9 LF SCF (2-3) Paved Kv= 20.3 fps
0.6	39	0.0050	1.14		Shallow Concentrated Flow, 39 LF SCF (3-4) Unpaved Kv= 16.1 fps
0.2	25	0.0092	1.95		Shallow Concentrated Flow, 25 LF SCF (4-5) Paved Kv= 20.3 fps
0.4	31	0.0081	1.45		Shallow Concentrated Flow, 31 LF SCF (5-6) Unpaved Kv= 16.1 fps
5.1	134	Total			

Subcatchment EX-2: Existing Drainage towards Roome Avenue

Summary for Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Runoff = 0.85 cfs @ 12.26 hrs, Volume= 3,913 cf, Depth= 1.77"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

Area (sf)	CN	Description
* 255	98	Impervious
2,009	96	Gravel surface, HSG B
24,269	61	>75% Grass cover, Good, HSG B
26,533	64	Weighted Average
26,278	64	99.04% Pervious Area
255	98	0.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	100	0.0053	0.11		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	77	0.0111	1.70		Shallow Concentrated Flow, 77 LF SCF (2-3) Unpaved Kv= 16.1 fps
16.6	177	Total			

Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Hydrograph



Summary for Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road


Runoff = 5.93 cfs @ 12.10 hrs, Volume= 19,344 cf, Depth= 4.27"

Routed to Pond B-1 : Infiltration Basin Along Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

	Area (sf)	CN	Description
	11,512	61	>75% Grass cover, Good, HSG B
*	27,825	98	Roof Area
*	15,087	98	Impervious Area
	54,424	90	Weighted Average
	11,512	61	21.15% Pervious Area
	42,912	98	78.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.0	12	0.0127	0.10		Sheet Flow, 12 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	23	0.0167	2.62		Shallow Concentrated Flow, 23 LF SCF (2-3) Paved Kv= 20.3 fps
0.0	21	0.2500	8.05		Shallow Concentrated Flow, 21 LF SCF (3-4) Unpaved Kv= 16.1 fps
2.1	56	Total			

Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Summary for Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Runoff = 1.64 cfs @ 12.10 hrs, Volume= 5,453 cf, Depth= 4.97"

Routed to Pond B-2 : Porous Pavement Within Tandem Spaces


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

Area (sf)	CN	Description
132	61	>75% Grass cover, Good, HSG B
* 3,564	98	Porous Pavement
* 9,475	98	Impervious Area
13,171	98	Weighted Average
132	61	1.00% Pervious Area
13,039	98	99.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	15	0.0127	0.10		Sheet Flow, 15 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.2	41	0.0250	3.21		Shallow Concentrated Flow, 41 LF SCF (2-3)
					Paved Kv= 20.3 fps
2.6	56	Total			

Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Hydrograph



Summary for Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Runoff = 2.88 cfs @ 12.18 hrs, Volume= 10,937 cf, Depth= 2.49"

Routed to Pond B-3 : Infiltration Basin Along Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

Area (sf)	CN	Description
27,952	61	>75% Grass cover, Good, HSG B
* 7,880	98	Impervious Area
* 16,788	80	Turf Field
52,620	73	Weighted Average
44,740	68	85.02% Pervious Area
7,880	98	14.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	100	0.0175	0.17		Sheet Flow, 100 LF Sheet Flow Grass: Short n= 0.150 P2= 3.54"
0.3	33	0.0175	2.13		Shallow Concentrated Flow, 33 LF SCF (2-3) Unpaved Kv= 16.1 fps
10.1	133	Total			

Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Hydrograph



Summary for Subcatchment P-1D: Undetained Flow to Sunset Road

Runoff = 0.59 cfs @ 12.17 hrs, Volume= 2,273 cf, Depth= 1.97"

Routed to Link POI-1 : Proposed Drainage to Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

Area (sf)	CN	Description
12,038	61	>75% Grass cover, Good, HSG B
* 1,805	98	Impervious Area
13,843	66	Weighted Average
12,038	61	86.96% Pervious Area
1,805	98	13.04% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.5	100	0.0250	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	87	0.0135	1.87		Shallow Concentrated Flow, 87 LF SCF (2-3) Unpaved Kv= 16.1 fps
9.3	187	Total			

Subcatchment P-1D: Undetained Flow to Sunset Road

Hydrograph



Summary for Subcatchment P-2: Proposed Drainage to Roome Avenue

Runoff = 2.25 cfs @ 12.15 hrs, Volume= 7,633 cf, Depth= 2.48"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

	Area (sf)	CN	Description
	17,643	61	>75% Grass cover, Good, HSG B
*	3,464	98	Impervious Area
*	15,872	80	Turf Field
	36,979	73	Weighted Average
	33,515	70	90.63% Pervious Area
	3,464	98	9.37% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.6	92	0.0285	0.20		Sheet Flow, 92 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"

Subcatchment P-2: Proposed Drainage to Roome Avenue

Hydrograph



Summary for Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Runoff = 0.18 cfs @ 12.11 hrs, Volume= 489 cf, Depth= 2.47"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 10-Year Rainfall=5.24"

Area (sf)	CN	Description
834	61	>75% Grass cover, Good, HSG B
* 1,540	80	Turf Field
2,374	73	Weighted Average
2,374	73	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.7	16	0.0115	0.10		Sheet Flow, 14 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.0	5	0.0115	1.73		Shallow Concentrated Flow, 5 LF SCF (2-3) Unpaved Kv= 16.1 fps
2.7	21	Total			

Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Hydrograph



Summary for Pond B-1: Infiltration Basin Along Sunset Road

Inflow Area = 54,424 sf, 78.85% Impervious, Inflow Depth = 4.27" for 10-Year event
 Inflow = 5.93 cfs @ 12.10 hrs, Volume= 19,344 cf
 Outflow = 0.78 cfs @ 12.61 hrs, Volume= 19,344 cf, Atten= 87%, Lag= 30.8 min
 Discarded = 0.09 cfs @ 12.61 hrs, Volume= 9,794 cf
 Primary = 0.69 cfs @ 12.61 hrs, Volume= 9,550 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.88' @ 12.61 hrs Surf.Area= 6,847 sf Storage= 9,596 cf


Plug-Flow detention time= 443.0 min calculated for 19,341 cf (100% of inflow)
 Center-of-Mass det. time= 443.2 min (1,198.1 - 754.9)

Volume	Invert	Avail.Storage	Storage Description		
#1	187.00'	14,171 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
187.00	3,406	592.8	0	0	3,406
188.00	5,212	611.7	4,277	4,277	5,315
189.00	7,076	630.5	6,120	10,397	7,275
189.50	8,029	639.9	3,774	14,171	8,276

Device	Routing	Invert	Outlet Devices
#1	Primary	186.50'	12.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 186.50' / 185.75' S= 0.0250 ' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.85'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.50'	12.0" W x 2.5" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.15'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	187.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.09 cfs @ 12.61 hrs HW=188.88' (Free Discharge)
 ↳ **5=Exfiltration** (Controls 0.09 cfs)

Primary OutFlow Max=0.69 cfs @ 12.61 hrs HW=188.88' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.69 cfs of 5.19 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.16 cfs @ 4.65 fps)
 ↳ **3=Orifice/Grate** (Orifice Controls 0.53 cfs @ 2.54 fps)
 ↳ **4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-1: Infiltration Basin Along Sunset Road

Summary for Pond B-2: Porous Pavement Within Tandem Spaces

Inflow Area = 13,171 sf, 99.00% Impervious, Inflow Depth = 4.97" for 10-Year event
 Inflow = 1.64 cfs @ 12.10 hrs, Volume= 5,453 cf
 Outflow = 0.22 cfs @ 12.56 hrs, Volume= 5,453 cf, Atten= 86%, Lag= 27.7 min
 Discarded = 0.05 cfs @ 12.56 hrs, Volume= 3,556 cf
 Primary = 0.17 cfs @ 12.56 hrs, Volume= 1,897 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.37' @ 12.56 hrs Surf.Area= 3,564 sf Storage= 2,163 cf

Plug-Flow detention time= 163.2 min calculated for 5,453 cf (100% of inflow)
 Center-of-Mass det. time= 163.2 min (908.9 - 745.7)


Volume	Invert	Avail.Storage	Storage Description
#1	186.85'	2,851 cf	Custom Stage Data (Irregular) Listed below (Recalc) 7,128 cf Overall x 40.0% Voids

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
186.85	3,564	306.0	0	0	3,564
187.85	3,564	306.0	3,564	3,564	3,870
188.85	3,564	306.0	3,564	7,128	4,176

Device	Routing	Invert	Outlet Devices
#1	Primary	186.85'	12.0" Round Culvert L= 135.0' Ke= 0.500 Inlet / Outlet Invert= 186.85' / 185.75' S= 0.0081 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.45'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.35'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#4	Discarded	186.85'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 12.56 hrs HW=188.37' (Free Discharge)
 ↳ **4=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=0.17 cfs @ 12.56 hrs HW=188.37' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.17 cfs of 3.35 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.15 cfs @ 4.34 fps)
 ↳ **3=Broad-Crested Rectangular Weir** (Weir Controls 0.02 cfs @ 0.36 fps)

Pond B-2: Porous Pavement Within Tandem Spaces

Summary for Pond B-3: Infiltration Basin Along Sunset Road

Inflow Area = 52,620 sf, 14.98% Impervious, Inflow Depth = 2.49" for 10-Year event
 Inflow = 2.88 cfs @ 12.18 hrs, Volume= 10,937 cf
 Outflow = 0.69 cfs @ 12.63 hrs, Volume= 10,937 cf, Atten= 76%, Lag= 27.2 min
 Discarded = 0.05 cfs @ 12.63 hrs, Volume= 3,241 cf
 Primary = 0.64 cfs @ 12.63 hrs, Volume= 7,696 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 189.14' @ 12.63 hrs Surf.Area= 3,761 sf Storage= 3,659 cf

Plug-Flow detention time= 119.9 min calculated for 10,935 cf (100% of inflow)
 Center-of-Mass det. time= 120.0 min (951.7 - 831.8)

Volume	Invert	Avail.Storage	Storage Description		
#1	188.00'	7,255 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
188.00	2,670	308.6	0	0	2,670
189.00	3,625	227.5	3,135	3,135	6,140
190.00	4,635	346.3	4,120	7,255	11,572


Device	Routing	Invert	Outlet Devices
#1	Primary	187.50'	12.0" Round Culvert L= 325.0' Ke= 0.500 Inlet / Outlet Invert= 187.50' / 185.85' S= 0.0051 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	188.25'	6.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.80'	3.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.60'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	188.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.10' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 12.63 hrs HW=189.14' (Free Discharge)

↑**5=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=0.64 cfs @ 12.63 hrs HW=189.14' TW=0.00' (Dynamic Tailwater)


↑**1=Culvert** (Passes 0.64 cfs of 2.79 cfs potential flow)
 ↑**2=Orifice/Grate** (Orifice Controls 0.53 cfs @ 4.21 fps)
 ↑**3=Orifice/Grate** (Orifice Controls 0.11 cfs @ 2.24 fps)
 ↑**4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-3: Infiltration Basin Along Sunset Road

Summary for Link POI-1: Proposed Drainage to Sunset Road

Inflow Area = 134,058 sf, 48.96% Impervious, Inflow Depth = 1.92" for 10-Year event
Inflow = 1.69 cfs @ 12.23 hrs, Volume= 21,415 cf
Primary = 1.69 cfs @ 12.23 hrs, Volume= 21,415 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link POI-1: Proposed Drainage to Sunset Road

Summary for Subcatchment EX-1: Existing Drainage towards Sunset Road

Runoff = 9.18 cfs @ 12.19 hrs, Volume= 38,409 cf, Depth= 5.27"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
*	30,985	98	Impervious
	56,446	61	>75% Grass cover, Good, HSG B
	87,431	74	Weighted Average
	56,446	61	64.56% Pervious Area
	30,985	98	35.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.4	100	0.0258	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
1.6	86	0.0031	0.90		Shallow Concentrated Flow, 86 LF SCF (2-3) Unpaved Kv= 16.1 fps
0.1	10	0.0200	2.87		Shallow Concentrated Flow, 10 LF SCF (3-4) Paved Kv= 20.3 fps
1.7	151	0.0080	1.44		Shallow Concentrated Flow, 151 LF SCF (4-5) Unpaved Kv= 16.1 fps
11.8	347	Total			

Subcatchment EX-1: Existing Drainage towards Sunset Road

Hydrograph




Summary for Subcatchment EX-2: Existing Drainage towards Roome Avenue

Runoff = 7.33 cfs @ 12.12 hrs, Volume= 23,345 cf, Depth= 4.71"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
*	13,506	98	Impervious
	45,941	61	>75% Grass cover, Good, HSG B
	59,447	69	Weighted Average
	45,941	61	77.28% Pervious Area
	13,506	98	22.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.8	30	0.0170	0.13		Sheet Flow, 30 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	9	0.0110	2.13		Shallow Concentrated Flow, 9 LF SCF (2-3) Paved Kv= 20.3 fps
0.6	39	0.0050	1.14		Shallow Concentrated Flow, 39 LF SCF (3-4) Unpaved Kv= 16.1 fps
0.2	25	0.0092	1.95		Shallow Concentrated Flow, 25 LF SCF (4-5) Paved Kv= 20.3 fps
0.4	31	0.0081	1.45		Shallow Concentrated Flow, 31 LF SCF (5-6) Unpaved Kv= 16.1 fps
5.1	134	Total			

Subcatchment EX-2: Existing Drainage towards Roome Avenue


Summary for Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Runoff = 2.05 cfs @ 12.25 hrs, Volume= 9,068 cf, Depth= 4.10"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
* 255	98	Impervious
2,009	96	Gravel surface, HSG B
24,269	61	>75% Grass cover, Good, HSG B
26,533	64	Weighted Average
26,278	64	99.04% Pervious Area
255	98	0.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	100	0.0053	0.11		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	77	0.0111	1.70		Shallow Concentrated Flow, 77 LF SCF (2-3) Unpaved Kv= 16.1 fps
16.6	177	Total			

Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Summary for Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road


Runoff = 9.95 cfs @ 12.10 hrs, Volume= 32,564 cf, Depth= 7.18"

Routed to Pond B-1 : Infiltration Basin Along Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
	11,512	61	>75% Grass cover, Good, HSG B
*	27,825	98	Roof Area
*	15,087	98	Impervious Area
	54,424	90	Weighted Average
	11,512	61	21.15% Pervious Area
	42,912	98	78.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.0	12	0.0127	0.10		Sheet Flow, 12 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	23	0.0167	2.62		Shallow Concentrated Flow, 23 LF SCF (2-3) Paved Kv= 20.3 fps
0.0	21	0.2500	8.05		Shallow Concentrated Flow, 21 LF SCF (3-4) Unpaved Kv= 16.1 fps
2.1	56	Total			

Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Summary for Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Runoff = 2.63 cfs @ 12.10 hrs, Volume= 8,853 cf, Depth= 8.07"

Routed to Pond B-2 : Porous Pavement Within Tandem Spaces


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
132	61	>75% Grass cover, Good, HSG B
* 3,564	98	Porous Pavement
* 9,475	98	Impervious Area
13,171	98	Weighted Average
132	61	1.00% Pervious Area
13,039	98	99.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	15	0.0127	0.10		Sheet Flow, 15 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.2	41	0.0250	3.21		Shallow Concentrated Flow, 41 LF SCF (2-3)
					Paved Kv= 20.3 fps
2.6	56	Total			

Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Hydrograph



Summary for Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Runoff = 5.95 cfs @ 12.17 hrs, Volume= 22,218 cf, Depth= 5.07"

Routed to Pond B-3 : Infiltration Basin Along Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
27,952	61	>75% Grass cover, Good, HSG B
* 7,880	98	Impervious Area
* 16,788	80	Turf Field
52,620	73	Weighted Average
44,740	68	85.02% Pervious Area
7,880	98	14.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	100	0.0175	0.17		Sheet Flow, 100 LF Sheet Flow Grass: Short n= 0.150 P2= 3.54"
0.3	33	0.0175	2.13		Shallow Concentrated Flow, 33 LF SCF (2-3) Unpaved Kv= 16.1 fps
10.1	133	Total			

Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Hydrograph



Summary for Subcatchment P-1D: Undetained Flow to Sunset Road


Runoff = 1.35 cfs @ 12.17 hrs, Volume= 4,945 cf, Depth= 4.29"

Routed to Link POI-1 : Proposed Drainage to Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
12,038	61	>75% Grass cover, Good, HSG B
* 1,805	98	Impervious Area
13,843	66	Weighted Average
12,038	61	86.96% Pervious Area
1,805	98	13.04% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.5	100	0.0250	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	87	0.0135	1.87		Shallow Concentrated Flow, 87 LF SCF (2-3) Unpaved Kv= 16.1 fps
9.3	187	Total			

Subcatchment P-1D: Undetained Flow to Sunset Road


Summary for Subcatchment P-2: Proposed Drainage to Roome Avenue

Runoff = 4.64 cfs @ 12.15 hrs, Volume= 15,654 cf, Depth= 5.08"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
	17,643	61	>75% Grass cover, Good, HSG B
*	3,464	98	Impervious Area
*	15,872	80	Turf Field
	36,979	73	Weighted Average
	33,515	70	90.63% Pervious Area
	3,464	98	9.37% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.6	92	0.0285	0.20		Sheet Flow, 92 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"

Subcatchment P-2: Proposed Drainage to Roome Avenue

Summary for Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Runoff = 0.36 cfs @ 12.11 hrs, Volume= 1,013 cf, Depth= 5.12"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
834	61	>75% Grass cover, Good, HSG B
* 1,540	80	Turf Field
2,374	73	Weighted Average
2,374	73	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.7	16	0.0115	0.10		Sheet Flow, 14 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.0	5	0.0115	1.73		Shallow Concentrated Flow, 5 LF SCF (2-3)
					Unpaved Kv= 16.1 fps
2.7	21	Total			

Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Hydrograph



Summary for Pond B-1: Infiltration Basin Along Sunset Road

Inflow Area = 54,424 sf, 78.85% Impervious, Inflow Depth = 7.18" for 100-Year event
 Inflow = 9.95 cfs @ 12.10 hrs, Volume= 32,564 cf
 Outflow = 3.39 cfs @ 12.21 hrs, Volume= 32,564 cf, Atten= 66%, Lag= 7.0 min
 Discarded = 0.11 cfs @ 12.21 hrs, Volume= 10,979 cf
 Primary = 3.28 cfs @ 12.21 hrs, Volume= 21,585 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 189.49' @ 12.21 hrs Surf.Area= 8,006 sf Storage= 14,078 cf


Plug-Flow detention time= 334.5 min calculated for 32,559 cf (100% of inflow)
 Center-of-Mass det. time= 334.7 min (1,084.7 - 750.0)

Volume	Invert	Avail.Storage	Storage Description		
#1	187.00'	14,171 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
187.00	3,406	592.8	0	0	3,406
188.00	5,212	611.7	4,277	4,277	5,315
189.00	7,076	630.5	6,120	10,397	7,275
189.50	8,029	639.9	3,774	14,171	8,276

Device	Routing	Invert	Outlet Devices
#1	Primary	186.50'	12.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 186.50' / 185.75' S= 0.0250 ' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.85'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.50'	12.0" W x 2.5" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.15'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	187.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.11 cfs @ 12.21 hrs HW=189.49' (Free Discharge)
 ↳ **5=Exfiltration** (Controls 0.11 cfs)

Primary OutFlow Max=3.28 cfs @ 12.21 hrs HW=189.49' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 3.28 cfs of 5.97 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.20 cfs @ 5.96 fps)
 ↳ **3=Orifice/Grate** (Orifice Controls 0.94 cfs @ 4.52 fps)
 ↳ **4=Broad-Crested Rectangular Weir** (Weir Controls 2.13 cfs @ 1.58 fps)

Pond B-1: Infiltration Basin Along Sunset Road

Summary for Pond B-2: Porous Pavement Within Tandem Spaces

Inflow Area = 13,171 sf, 99.00% Impervious, Inflow Depth = 8.07" for 100-Year event
 Inflow = 2.63 cfs @ 12.10 hrs, Volume= 8,853 cf
 Outflow = 2.27 cfs @ 12.12 hrs, Volume= 8,853 cf, Atten= 14%, Lag= 1.5 min
 Discarded = 0.05 cfs @ 12.12 hrs, Volume= 4,245 cf
 Primary = 2.22 cfs @ 12.12 hrs, Volume= 4,608 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.68' @ 12.12 hrs Surf.Area= 3,564 sf Storage= 2,607 cf

Plug-Flow detention time= 135.4 min calculated for 8,852 cf (100% of inflow)
 Center-of-Mass det. time= 135.5 min (874.3 - 738.8)


Volume	Invert	Avail.Storage	Storage Description
#1	186.85'	2,851 cf	Custom Stage Data (Irregular) Listed below (Recalc) 7,128 cf Overall x 40.0% Voids

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
186.85	3,564	306.0	0	0	3,564
187.85	3,564	306.0	3,564	3,564	3,870
188.85	3,564	306.0	3,564	7,128	4,176

Device	Routing	Invert	Outlet Devices
#1	Primary	186.85'	12.0" Round Culvert L= 135.0' Ke= 0.500 Inlet / Outlet Invert= 186.85' / 185.75' S= 0.0081 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.45'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.35'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#4	Discarded	186.85'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 12.12 hrs HW=188.68' (Free Discharge)
 ↳ **4=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=2.21 cfs @ 12.12 hrs HW=188.68' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 2.21 cfs of 3.65 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.17 cfs @ 5.10 fps)
 ↳ **3=Broad-Crested Rectangular Weir** (Weir Controls 2.04 cfs @ 1.55 fps)

Pond B-2: Porous Pavement Within Tandem Spaces

Summary for Pond B-3: Infiltration Basin Along Sunset Road

Inflow Area = 52,620 sf, 14.98% Impervious, Inflow Depth = 5.07" for 100-Year event
 Inflow = 5.95 cfs @ 12.17 hrs, Volume= 22,218 cf
 Outflow = 2.75 cfs @ 12.35 hrs, Volume= 22,218 cf, Atten= 54%, Lag= 10.8 min
 Discarded = 0.06 cfs @ 12.35 hrs, Volume= 3,791 cf
 Primary = 2.69 cfs @ 12.35 hrs, Volume= 18,427 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 189.89' @ 12.35 hrs Surf.Area= 4,521 sf Storage= 6,767 cf

Plug-Flow detention time= 94.9 min calculated for 22,215 cf (100% of inflow)
 Center-of-Mass det. time= 95.0 min (912.6 - 817.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	188.00'	7,255 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
188.00	2,670	308.6	0	0	2,670
189.00	3,625	227.5	3,135	3,135	6,140
190.00	4,635	346.3	4,120	7,255	11,572

Device	Routing	Invert	Outlet Devices
#1	Primary	187.50'	12.0" Round Culvert L= 325.0' Ke= 0.500 Inlet / Outlet Invert= 187.50' / 185.85' S= 0.0051 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	188.25'	6.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.80'	3.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.60'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	188.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.10' Phase-In= 0.01'

Discarded OutFlow Max=0.06 cfs @ 12.35 hrs HW=189.89' (Free Discharge)

↑**5=Exfiltration** (Controls 0.06 cfs)


Primary OutFlow Max=2.69 cfs @ 12.35 hrs HW=189.89' TW=0.00' (Dynamic Tailwater)

↑**1=Culvert** (Passes 2.69 cfs of 3.21 cfs potential flow)

↑**2=Orifice/Grate** (Orifice Controls 0.74 cfs @ 5.93 fps)

↑**3=Orifice/Grate** (Orifice Controls 0.23 cfs @ 4.74 fps)


↑**4=Broad-Crested Rectangular Weir** (Weir Controls 1.72 cfs @ 1.46 fps)

Pond B-3: Infiltration Basin Along Sunset Road

Summary for Link POI-1: Proposed Drainage to Sunset Road

Inflow Area = 134,058 sf, 48.96% Impervious, Inflow Depth = 4.44" for 100-Year event
Inflow = 7.32 cfs @ 12.14 hrs, Volume= 49,566 cf
Primary = 7.32 cfs @ 12.14 hrs, Volume= 49,566 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

Link POI-1: Proposed Drainage to Sunset Road

Summary for Subcatchment EX-1: Existing Drainage towards Sunset Road

Runoff = 1.75 cfs @ 1.17 hrs, Volume= 2,671 cf, Depth= 0.37"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

	Area (sf)	CN	Description
*	30,985	98	Impervious
	56,446	61	>75% Grass cover, Good, HSG B
	87,431	74	Weighted Average
	56,446	61	64.56% Pervious Area
	30,985	98	35.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.4	100	0.0258	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
1.6	86	0.0031	0.90		Shallow Concentrated Flow, 86 LF SCF (2-3) Unpaved Kv= 16.1 fps
0.1	10	0.0200	2.87		Shallow Concentrated Flow, 10 LF SCF (3-4) Paved Kv= 20.3 fps
1.7	151	0.0080	1.44		Shallow Concentrated Flow, 151 LF SCF (4-5) Unpaved Kv= 16.1 fps
11.8	347	Total			

Subcatchment EX-1: Existing Drainage towards Sunset Road

Hydrograph




Summary for Subcatchment EX-2: Existing Drainage towards Roome Avenue

Runoff = 0.92 cfs @ 1.10 hrs, Volume= 1,164 cf, Depth= 0.24"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

	Area (sf)	CN	Description
*	13,506	98	Impervious
	45,941	61	>75% Grass cover, Good, HSG B
	59,447	69	Weighted Average
	45,941	61	77.28% Pervious Area
	13,506	98	22.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.8	30	0.0170	0.13		Sheet Flow, 30 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	9	0.0110	2.13		Shallow Concentrated Flow, 9 LF SCF (2-3) Paved Kv= 20.3 fps
0.6	39	0.0050	1.14		Shallow Concentrated Flow, 39 LF SCF (3-4) Unpaved Kv= 16.1 fps
0.2	25	0.0092	1.95		Shallow Concentrated Flow, 25 LF SCF (4-5) Paved Kv= 20.3 fps
0.4	31	0.0081	1.45		Shallow Concentrated Flow, 31 LF SCF (5-6) Unpaved Kv= 16.1 fps
5.1	134	Total			

Subcatchment EX-2: Existing Drainage towards Roome Avenue

Summary for Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Runoff = 0.01 cfs @ 1.23 hrs, Volume= 28 cf, Depth= 0.01"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

	Area (sf)	CN	Description
*	255	98	Impervious
	2,009	96	Gravel surface, HSG B
	24,269	61	>75% Grass cover, Good, HSG B
	26,533	64	Weighted Average
	26,278	64	99.04% Pervious Area
	255	98	0.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	100	0.0053	0.11		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	77	0.0111	1.70		Shallow Concentrated Flow, 77 LF SCF (2-3) Unpaved Kv= 16.1 fps
16.6	177	Total			

Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Hydrograph



Summary for Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Runoff = 3.03 cfs @ 1.08 hrs, Volume= 3,700 cf, Depth= 0.82"

Routed to Pond B-1 : Infiltration Basin Along Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

Area (sf)	CN	Description
11,512	61	>75% Grass cover, Good, HSG B
* 27,825	98	Roof Area
* 15,087	98	Impervious Area
54,424	90	Weighted Average
11,512	61	21.15% Pervious Area
42,912	98	78.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.0	12	0.0127	0.10		Sheet Flow, 12 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	23	0.0167	2.62		Shallow Concentrated Flow, 23 LF SCF (2-3) Paved Kv= 20.3 fps
0.0	21	0.2500	8.05		Shallow Concentrated Flow, 21 LF SCF (3-4) Unpaved Kv= 16.1 fps
2.1	56	Total			

Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Hydrograph



Summary for Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Runoff = 0.92 cfs @ 1.08 hrs, Volume= 1,124 cf, Depth= 1.02"
Routed to Pond B-2 : Porous Pavement Within Tandem Spaces


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

Area (sf)	CN	Description
132	61	>75% Grass cover, Good, HSG B
* 3,564	98	Porous Pavement
* 9,475	98	Impervious Area
13,171	98	Weighted Average
132	61	1.00% Pervious Area
13,039	98	99.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	15	0.0127	0.10		Sheet Flow, 15 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.2	41	0.0250	3.21		Shallow Concentrated Flow, 41 LF SCF (2-3) Paved Kv= 20.3 fps
2.6	56	Total			

Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Hydrograph



Summary for Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Runoff = 0.47 cfs @ 1.15 hrs, Volume= 750 cf, Depth= 0.17"
 Routed to Pond B-3 : Infiltration Basin Along Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 NJ DEP 2-hr WQv Rainfall=1.25"

Area (sf)	CN	Description
27,952	61	>75% Grass cover, Good, HSG B
* 7,880	98	Impervious Area
* 16,788	80	Turf Field
52,620	73	Weighted Average
44,740	68	85.02% Pervious Area
7,880	98	14.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	100	0.0175	0.17		Sheet Flow, 100 LF Sheet Flow Grass: Short n= 0.150 P2= 3.54"
0.3	33	0.0175	2.13		Shallow Concentrated Flow, 33 LF SCF (2-3) Unpaved Kv= 16.1 fps
10.1	133	Total			

Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Hydrograph



Summary for Subcatchment P-1D: Undetained Flow to Sunset Road

Runoff = 0.11 cfs @ 1.14 hrs, Volume= 156 cf, Depth= 0.13"

Routed to Link POI-1 : Proposed Drainage to Sunset Road


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

Area (sf)	CN	Description
12,038	61	>75% Grass cover, Good, HSG B
* 1,805	98	Impervious Area
13,843	66	Weighted Average
12,038	61	86.96% Pervious Area
1,805	98	13.04% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.5	100	0.0250	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	87	0.0135	1.87		Shallow Concentrated Flow, 87 LF SCF (2-3) Unpaved Kv= 16.1 fps
9.3	187	Total			

Subcatchment P-1D: Undetained Flow to Sunset Road

Hydrograph



Summary for Subcatchment P-2: Proposed Drainage to Roome Avenue

Runoff = 0.22 cfs @ 1.12 hrs, Volume= 391 cf, Depth= 0.13"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

	Area (sf)	CN	Description
	17,643	61	>75% Grass cover, Good, HSG B
*	3,464	98	Impervious Area
*	15,872	80	Turf Field
	36,979	73	Weighted Average
	33,515	70	90.63% Pervious Area
	3,464	98	9.37% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.6	92	0.0285	0.20		Sheet Flow, 92 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"

Subcatchment P-2: Proposed Drainage to Roome Avenue

Hydrograph



Summary for Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Runoff = 0.01 cfs @ 1.11 hrs, Volume= 12 cf, Depth= 0.06"


Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NJ DEP 2-hr WQv Rainfall=1.25"

Area (sf)	CN	Description
834	61	>75% Grass cover, Good, HSG B
* 1,540	80	Turf Field
2,374	73	Weighted Average
2,374	73	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.7	16	0.0115	0.10		Sheet Flow, 14 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.0	5	0.0115	1.73		Shallow Concentrated Flow, 5 LF SCF (2-3)
					Unpaved Kv= 16.1 fps
2.7	21	Total			

Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Hydrograph



Summary for Pond B-1: Infiltration Basin Along Sunset Road

Inflow Area = 54,424 sf, 78.85% Impervious, Inflow Depth = 0.82" for WQv event
 Inflow = 3.03 cfs @ 1.08 hrs, Volume= 3,700 cf
 Outflow = 0.06 cfs @ 2.03 hrs, Volume= 3,700 cf, Atten= 98%, Lag= 56.7 min
 Discarded = 0.06 cfs @ 2.03 hrs, Volume= 3,700 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 187.83' @ 2.03 hrs Surf.Area= 4,869 sf Storage= 3,397 cf


Plug-Flow detention time= 532.5 min calculated for 3,700 cf (100% of inflow)
 Center-of-Mass det. time= 532.5 min (599.1 - 66.7)

Volume	Invert	Avail.Storage	Storage Description		
#1	187.00'	14,171 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
187.00	3,406	592.8	0	0	3,406
188.00	5,212	611.7	4,277	4,277	5,315
189.00	7,076	630.5	6,120	10,397	7,275
189.50	8,029	639.9	3,774	14,171	8,276

Device	Routing	Invert	Outlet Devices
#1	Primary	186.50'	12.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 186.50' / 185.75' S= 0.0250 ' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.85'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.50'	12.0" W x 2.5" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.15'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	187.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.06 cfs @ 2.03 hrs HW=187.83' (Free Discharge)
 ↳ **5=Exfiltration** (Controls 0.06 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=187.00' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.00 cfs of 0.95 cfs potential flow)
 ↳ **2=Orifice/Grate** (Controls 0.00 cfs)
 ↳ **3=Orifice/Grate** (Controls 0.00 cfs)
 ↳ **4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-1: Infiltration Basin Along Sunset Road

Summary for Pond B-2: Porous Pavement Within Tandem Spaces

Inflow Area = 13,171 sf, 99.00% Impervious, Inflow Depth = 1.02" for WQv event
 Inflow = 0.92 cfs @ 1.08 hrs, Volume= 1,124 cf
 Outflow = 0.05 cfs @ 1.80 hrs, Volume= 1,124 cf, Atten= 95%, Lag= 42.8 min
 Discarded = 0.05 cfs @ 1.80 hrs, Volume= 1,122 cf
 Primary = 0.00 cfs @ 1.80 hrs, Volume= 2 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 187.48' @ 1.80 hrs Surf.Area= 3,564 sf Storage= 896 cf

Plug-Flow detention time= 177.7 min calculated for 1,124 cf (100% of inflow)
 Center-of-Mass det. time= 177.7 min (244.8 - 67.1)


Volume	Invert	Avail.Storage	Storage Description
#1	186.85'	2,851 cf	Custom Stage Data (Irregular) Listed below (Recalc) 7,128 cf Overall x 40.0% Voids

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
186.85	3,564	306.0	0	0	3,564
187.85	3,564	306.0	3,564	3,564	3,870
188.85	3,564	306.0	3,564	7,128	4,176

Device	Routing	Invert	Outlet Devices
#1	Primary	186.85'	12.0" Round Culvert L= 135.0' Ke= 0.500 Inlet / Outlet Invert= 186.85' / 185.75' S= 0.0081 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.45'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.35'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#4	Discarded	186.85'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 1.80 hrs HW=187.48' (Free Discharge)
 ↳ **4=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=0.00 cfs @ 1.80 hrs HW=187.48' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 0.00 cfs of 1.34 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.00 cfs @ 0.57 fps)
 ↳ **3=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-2: Porous Pavement Within Tandem Spaces

Summary for Pond B-3: Infiltration Basin Along Sunset Road

Inflow Area = 52,620 sf, 14.98% Impervious, Inflow Depth = 0.17" for WQv event
 Inflow = 0.47 cfs @ 1.15 hrs, Volume= 750 cf
 Outflow = 0.03 cfs @ 2.02 hrs, Volume= 750 cf, Atten= 93%, Lag= 52.5 min
 Discarded = 0.03 cfs @ 2.02 hrs, Volume= 750 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.21' @ 2.02 hrs Surf.Area= 2,859 sf Storage= 581 cf

Plug-Flow detention time= 157.1 min calculated for 750 cf (100% of inflow)
 Center-of-Mass det. time= 157.1 min (233.7 - 76.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	188.00'	7,255 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
188.00	2,670	308.6	0	0	2,670
189.00	3,625	227.5	3,135	3,135	6,140
190.00	4,635	346.3	4,120	7,255	11,572

Device	Routing	Invert	Outlet Devices
#1	Primary	187.50'	12.0" Round Culvert L= 325.0' Ke= 0.500 Inlet / Outlet Invert= 187.50' / 185.85' S= 0.0051 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	188.25'	6.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.80'	3.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.60'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	188.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.10' Phase-In= 0.01'

Discarded OutFlow Max=0.03 cfs @ 2.02 hrs HW=188.21' (Free Discharge)

↑ **5=Exfiltration** (Controls 0.03 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=188.00' TW=0.00' (Dynamic Tailwater)


↑ **1=Culvert** (Passes 0.00 cfs of 0.75 cfs potential flow)

↑ **2=Orifice/Grate** (Controls 0.00 cfs)

↑ **3=Orifice/Grate** (Controls 0.00 cfs)

↑ **4=Broad-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond B-3: Infiltration Basin Along Sunset Road



Summary for Link POI-1: Proposed Drainage to Sunset Road

Inflow Area = 134,058 sf, 48.96% Impervious, Inflow Depth = 0.01" for WQv event
Inflow = 0.11 cfs @ 1.14 hrs, Volume= 157 cf
Primary = 0.11 cfs @ 1.14 hrs, Volume= 157 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs


Link POI-1: Proposed Drainage to Sunset Road

TABLE OF CONTENTS**Project Reports**

- 1 Routing Diagram
- 2 Area Listing (all nodes)

2-Year Event

- 3 Subcat EX-1: Existing Drainage towards Sunset Road
- 4 Subcat EX-2: Existing Drainage towards Roome Avenue
- 6 Subcat EX-3: Existing Drainage towards Dewilde Drive
- 7 Subcat P-1A: Drainage to Infiltration Basin Along Sunset Road
- 8 Subcat P-1B: Drainage to Porous Pavement in Tandem Spaces
- 9 Subcat P-1C: Drainage to Infiltration Basin in Rear
- 10 Subcat P-1D: Undetained Flow to Sunset Road
- 11 Subcat P-2: Proposed Drainage to Roome Avenue
- 12 Subcat P-3: Proposed Drainage toward Dewilde Drive
- 13 Pond B-1: Infiltration Basin Along Sunset Road
- 15 Pond B-2: Porous Pavement Within Tandem Spaces
- 17 Pond B-3: Infiltration Basin Along Sunset Road
- 19 Link POI-1: Proposed Drainage to Sunset Road

10-Year Event

- 20 Subcat EX-1: Existing Drainage towards Sunset Road
- 21 Subcat EX-2: Existing Drainage towards Roome Avenue
- 23 Subcat EX-3: Existing Drainage towards Dewilde Drive
- 24 Subcat P-1A: Drainage to Infiltration Basin Along Sunset Road
- 25 Subcat P-1B: Drainage to Porous Pavement in Tandem Spaces
- 26 Subcat P-1C: Drainage to Infiltration Basin in Rear
- 27 Subcat P-1D: Undetained Flow to Sunset Road
- 28 Subcat P-2: Proposed Drainage to Roome Avenue
- 29 Subcat P-3: Proposed Drainage toward Dewilde Drive
- 30 Pond B-1: Infiltration Basin Along Sunset Road
- 32 Pond B-2: Porous Pavement Within Tandem Spaces
- 34 Pond B-3: Infiltration Basin Along Sunset Road
- 36 Link POI-1: Proposed Drainage to Sunset Road

100-Year Event

- 37 Subcat EX-1: Existing Drainage towards Sunset Road
- 38 Subcat EX-2: Existing Drainage towards Roome Avenue
- 40 Subcat EX-3: Existing Drainage towards Dewilde Drive
- 41 Subcat P-1A: Drainage to Infiltration Basin Along Sunset Road
- 42 Subcat P-1B: Drainage to Porous Pavement in Tandem Spaces
- 43 Subcat P-1C: Drainage to Infiltration Basin in Rear
- 44 Subcat P-1D: Undetained Flow to Sunset Road
- 45 Subcat P-2: Proposed Drainage to Roome Avenue
- 46 Subcat P-3: Proposed Drainage toward Dewilde Drive
- 47 Pond B-1: Infiltration Basin Along Sunset Road
- 49 Pond B-2: Porous Pavement Within Tandem Spaces

2022-09-21_HydroCAD

Prepared by Stonefield Engineering & Design

HydroCAD® 10.20-2f s/n 10626 © 2022 HydroCAD Software Solutions LLC

Table of Contents

Printed 9/30/2022

- 51 Pond B-3: Infiltration Basin Along Sunset Road
- 53 Link POI-1: Proposed Drainage to Sunset Road

WQv Event

- 54 Subcat EX-1: Existing Drainage towards Sunset Road
- 55 Subcat EX-2: Existing Drainage towards Roome Avenue
- 57 Subcat EX-3: Existing Drainage towards Dewilde Drive
- 58 Subcat P-1A: Drainage to Infiltration Basin Along Sunset Road
- 59 Subcat P-1B: Drainage to Porous Pavement in Tandem Spaces
- 60 Subcat P-1C: Drainage to Infiltration Basin in Rear
- 61 Subcat P-1D: Undetained Flow to Sunset Road
- 62 Subcat P-2: Proposed Drainage to Roome Avenue
- 63 Subcat P-3: Proposed Drainage toward Dewilde Drive
- 64 Pond B-1: Infiltration Basin Along Sunset Road
- 66 Pond B-2: Porous Pavement Within Tandem Spaces
- 68 Pond B-3: Infiltration Basin Along Sunset Road
- 70 Link POI-1: Proposed Drainage to Sunset Road

Summary for Subcatchment EX-1: Existing Drainage towards Sunset Road

Runoff = 9.18 cfs @ 12.19 hrs, Volume= 38,409 cf, Depth= 5.27"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
*	30,985	98	Impervious
	56,446	61	>75% Grass cover, Good, HSG B
	87,431	74	Weighted Average
	56,446	61	64.56% Pervious Area
	30,985	98	35.44% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.4	100	0.0258	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
1.6	86	0.0031	0.90		Shallow Concentrated Flow, 86 LF SCF (2-3) Unpaved Kv= 16.1 fps
0.1	10	0.0200	2.87		Shallow Concentrated Flow, 10 LF SCF (3-4) Paved Kv= 20.3 fps
1.7	151	0.0080	1.44		Shallow Concentrated Flow, 151 LF SCF (4-5) Unpaved Kv= 16.1 fps
11.8	347	Total			

Summary for Subcatchment EX-2: Existing Drainage towards Roome Avenue

Runoff = 7.33 cfs @ 12.12 hrs, Volume= 23,345 cf, Depth= 4.71"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
*	13,506	98	Impervious
	45,941	61	>75% Grass cover, Good, HSG B
	59,447	69	Weighted Average
	45,941	61	77.28% Pervious Area
	13,506	98	22.72% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.8	30	0.0170	0.13		Sheet Flow, 30 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	9	0.0110	2.13		Shallow Concentrated Flow, 9 LF SCF (2-3) Paved Kv= 20.3 fps
0.6	39	0.0050	1.14		Shallow Concentrated Flow, 39 LF SCF (3-4) Unpaved Kv= 16.1 fps
0.2	25	0.0092	1.95		Shallow Concentrated Flow, 25 LF SCF (4-5) Paved Kv= 20.3 fps
0.4	31	0.0081	1.45		Shallow Concentrated Flow, 31 LF SCF (5-6) Unpaved Kv= 16.1 fps
5.1	134	Total			

Summary for Subcatchment EX-3: Existing Drainage towards Dewilde Drive

Runoff = 2.05 cfs @ 12.25 hrs, Volume= 9,068 cf, Depth= 4.10"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
*	255	98	Impervious
	2,009	96	Gravel surface, HSG B
	24,269	61	>75% Grass cover, Good, HSG B
	26,533	64	Weighted Average
	26,278	64	99.04% Pervious Area
	255	98	0.96% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
15.8	100	0.0053	0.11		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	77	0.0111	1.70		Shallow Concentrated Flow, 77 LF SCF (2-3) Unpaved Kv= 16.1 fps
16.6	177	Total			

Summary for Subcatchment P-1A: Drainage to Infiltration Basin Along Sunset Road

Runoff = 9.95 cfs @ 12.10 hrs, Volume= 32,564 cf, Depth= 7.18"

Routed to Pond B-1 : Infiltration Basin Along Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
	11,512	61	>75% Grass cover, Good, HSG B
*	27,825	98	Roof Area
*	15,087	98	Impervious Area
	54,424	90	Weighted Average
	11,512	61	21.15% Pervious Area
	42,912	98	78.85% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.0	12	0.0127	0.10		Sheet Flow, 12 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.1	23	0.0167	2.62		Shallow Concentrated Flow, 23 LF SCF (2-3) Paved Kv= 20.3 fps
0.0	21	0.2500	8.05		Shallow Concentrated Flow, 21 LF SCF (3-4) Unpaved Kv= 16.1 fps
2.1	56	Total			

Summary for Subcatchment P-1B: Drainage to Porous Pavement in Tandem Spaces

Runoff = 2.63 cfs @ 12.10 hrs, Volume= 8,853 cf, Depth= 8.07"

Routed to Pond B-2 : Porous Pavement Within Tandem Spaces

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
132	61	>75% Grass cover, Good, HSG B
* 3,564	98	Porous Pavement
* 9,475	98	Impervious Area
13,171	98	Weighted Average
132	61	1.00% Pervious Area
13,039	98	99.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.4	15	0.0127	0.10		Sheet Flow, 15 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.2	41	0.0250	3.21		Shallow Concentrated Flow, 41 LF SCF (2-3) Paved Kv= 20.3 fps
2.6	56	Total			

Summary for Subcatchment P-1C: Drainage to Infiltration Basin in Rear

Runoff = 5.95 cfs @ 12.17 hrs, Volume= 22,218 cf, Depth= 5.07"

Routed to Pond B-3 : Infiltration Basin Along Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
	27,952	61	>75% Grass cover, Good, HSG B
*	7,880	98	Impervious Area
*	16,788	80	Turf Field
	52,620	73	Weighted Average
	44,740	68	85.02% Pervious Area
	7,880	98	14.98% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.8	100	0.0175	0.17		Sheet Flow, 100 LF Sheet Flow Grass: Short n= 0.150 P2= 3.54"
0.3	33	0.0175	2.13		Shallow Concentrated Flow, 33 LF SCF (2-3) Unpaved Kv= 16.1 fps
10.1	133	Total			

Summary for Subcatchment P-1D: Undetained Flow to Sunset Road

Runoff = 1.35 cfs @ 12.17 hrs, Volume= 4,945 cf, Depth= 4.29"

Routed to Link POI-1 : Proposed Drainage to Sunset Road

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
12,038	61	>75% Grass cover, Good, HSG B
* 1,805	98	Impervious Area
13,843	66	Weighted Average
12,038	61	86.96% Pervious Area
1,805	98	13.04% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
8.5	100	0.0250	0.20		Sheet Flow, 100 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"
0.8	87	0.0135	1.87		Shallow Concentrated Flow, 87 LF SCF (2-3) Unpaved Kv= 16.1 fps
9.3	187	Total			

Summary for Subcatchment P-2: Proposed Drainage to Roome Avenue

Runoff = 4.64 cfs @ 12.15 hrs, Volume= 15,654 cf, Depth= 5.08"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

	Area (sf)	CN	Description
	17,643	61	>75% Grass cover, Good, HSG B
*	3,464	98	Impervious Area
*	15,872	80	Turf Field
	36,979	73	Weighted Average
	33,515	70	90.63% Pervious Area
	3,464	98	9.37% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.6	92	0.0285	0.20		Sheet Flow, 92 LF Sheet Flow (1-2) Grass: Short n= 0.150 P2= 3.54"

Summary for Subcatchment P-3: Proposed Drainage toward Dewilde Drive

Runoff = 0.36 cfs @ 12.11 hrs, Volume= 1,013 cf, Depth= 5.12"

Runoff by SCS TR-20 method, UH=SCS, Split Pervious/Imperv., Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
NOAA 24-hr D 100-Year Rainfall=8.35"

Area (sf)	CN	Description
834	61	>75% Grass cover, Good, HSG B
* 1,540	80	Turf Field
2,374	73	Weighted Average
2,374	73	100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.7	16	0.0115	0.10		Sheet Flow, 14 LF Sheet Flow (1-2)
					Grass: Short n= 0.150 P2= 3.54"
0.0	5	0.0115	1.73		Shallow Concentrated Flow, 5 LF SCF (2-3)
					Unpaved Kv= 16.1 fps
2.7	21	Total			

Summary for Pond B-1: Infiltration Basin Along Sunset Road

Inflow Area = 54,424 sf, 78.85% Impervious, Inflow Depth = 7.18" for 100-Year event
 Inflow = 9.95 cfs @ 12.10 hrs, Volume= 32,564 cf
 Outflow = 3.39 cfs @ 12.21 hrs, Volume= 32,564 cf, Atten= 66%, Lag= 7.0 min
 Discarded = 0.11 cfs @ 12.21 hrs, Volume= 10,979 cf
 Primary = 3.28 cfs @ 12.21 hrs, Volume= 21,585 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 189.49' @ 12.21 hrs Surf.Area= 8,006 sf Storage= 14,078 cf

Plug-Flow detention time= 334.5 min calculated for 32,559 cf (100% of inflow)
 Center-of-Mass det. time= 334.7 min (1,084.7 - 750.0)

Volume	Invert	Avail.Storage	Storage Description		
#1	187.00'	14,171 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
187.00	3,406	592.8	0	0	3,406
188.00	5,212	611.7	4,277	4,277	5,315
189.00	7,076	630.5	6,120	10,397	7,275
189.50	8,029	639.9	3,774	14,171	8,276

Device	Routing	Invert	Outlet Devices
#1	Primary	186.50'	12.0" Round Culvert L= 30.0' Ke= 0.500 Inlet / Outlet Invert= 186.50' / 185.75' S= 0.0250 ' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.85'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.50'	12.0" W x 2.5" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.15'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	187.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.11 cfs @ 12.21 hrs HW=189.49' (Free Discharge)
 ↳ **5=Exfiltration** (Controls 0.11 cfs)

Primary OutFlow Max=3.28 cfs @ 12.21 hrs HW=189.49' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 3.28 cfs of 5.97 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.20 cfs @ 5.96 fps)
 ↳ **3=Orifice/Grate** (Orifice Controls 0.94 cfs @ 4.52 fps)
 ↳ **4=Broad-Crested Rectangular Weir** (Weir Controls 2.13 cfs @ 1.58 fps)

Stage-Discharge for Pond B-1: Infiltration Basin Along Sunset Road

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
187.00	0.00	0.00	0.00
187.10	0.04	0.04	0.00
187.20	0.04	0.04	0.00
187.30	0.05	0.05	0.00
187.40	0.05	0.05	0.00
187.50	0.05	0.05	0.00
187.60	0.06	0.06	0.00
187.70	0.06	0.06	0.00
187.80	0.06	0.06	0.00
187.90	0.07	0.06	0.00
188.00	0.10	0.07	0.03
188.10	0.13	0.07	0.06
188.20	0.15	0.07	0.08
188.30	0.17	0.08	0.10
188.40	0.19	0.08	0.11
188.50	0.20	0.08	0.12
188.60	0.32	0.09	0.23
188.70	0.52	0.09	0.43
188.80	0.68	0.09	0.59
188.90	0.80	0.10	0.70
189.00	0.90	0.10	0.80
189.10	0.98	0.10	0.88
189.20	1.18	0.11	1.08
189.30	1.76	0.11	1.65
189.40	2.55	0.11	2.44
189.50	3.51	0.12	3.40

Stage-Area-Storage for Pond B-1: Infiltration Basin Along Sunset Road

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
187.00	3,406	0
187.10	3,569	349
187.20	3,737	714
187.30	3,908	1,096
187.40	4,082	1,496
187.50	4,261	1,913
187.60	4,444	2,348
187.70	4,630	2,802
187.80	4,820	3,274
187.90	5,014	3,766
188.00	5,212	4,277
188.10	5,386	4,807
188.20	5,562	5,354
188.30	5,741	5,919
188.40	5,923	6,503
188.50	6,108	7,104
188.60	6,296	7,724
188.70	6,487	8,364
188.80	6,680	9,022
188.90	6,877	9,700
189.00	7,076	10,397
189.10	7,262	11,114
189.20	7,450	11,850
189.30	7,641	12,604
189.40	7,834	13,378
189.50	8,029	14,171

Summary for Pond B-2: Porous Pavement Within Tandem Spaces

Inflow Area = 13,171 sf, 99.00% Impervious, Inflow Depth = 8.07" for 100-Year event
 Inflow = 2.63 cfs @ 12.10 hrs, Volume= 8,853 cf
 Outflow = 2.27 cfs @ 12.12 hrs, Volume= 8,853 cf, Atten= 14%, Lag= 1.5 min
 Discarded = 0.05 cfs @ 12.12 hrs, Volume= 4,245 cf
 Primary = 2.22 cfs @ 12.12 hrs, Volume= 4,608 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 188.68' @ 12.12 hrs Surf.Area= 3,564 sf Storage= 2,607 cf

Plug-Flow detention time= 135.4 min calculated for 8,852 cf (100% of inflow)
 Center-of-Mass det. time= 135.5 min (874.3 - 738.8)

Volume	Invert	Avail.Storage	Storage Description
#1	186.85'	2,851 cf	Custom Stage Data (Irregular) Listed below (Recalc) 7,128 cf Overall x 40.0% Voids

Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
186.85	3,564	306.0	0	0	3,564
187.85	3,564	306.0	3,564	3,564	3,870
188.85	3,564	306.0	3,564	7,128	4,176

Device	Routing	Invert	Outlet Devices
#1	Primary	186.85'	12.0" Round Culvert L= 135.0' Ke= 0.500 Inlet / Outlet Invert= 186.85' / 185.75' S= 0.0081 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	187.45'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.35'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#4	Discarded	186.85'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.00' Phase-In= 0.01'

Discarded OutFlow Max=0.05 cfs @ 12.12 hrs HW=188.68' (Free Discharge)
 ↳ **4=Exfiltration** (Controls 0.05 cfs)

Primary OutFlow Max=2.21 cfs @ 12.12 hrs HW=188.68' TW=0.00' (Dynamic Tailwater)
 ↳ **1=Culvert** (Passes 2.21 cfs of 3.65 cfs potential flow)
 ↳ **2=Orifice/Grate** (Orifice Controls 0.17 cfs @ 5.10 fps)
 ↳ **3=Broad-Crested Rectangular Weir** (Weir Controls 2.04 cfs @ 1.55 fps)

Stage-Discharge for Pond B-2: Porous Pavement Within Tandem Spaces

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
186.85	0.00	0.00	0.00
186.95	0.04	0.04	0.00
187.05	0.04	0.04	0.00
187.15	0.04	0.04	0.00
187.25	0.04	0.04	0.00
187.35	0.04	0.04	0.00
187.45	0.04	0.04	0.00
187.55	0.06	0.05	0.02
187.65	0.10	0.05	0.05
187.75	0.12	0.05	0.07
187.85	0.14	0.05	0.09
187.95	0.15	0.05	0.10
188.05	0.16	0.05	0.12
188.15	0.18	0.05	0.13
188.25	0.19	0.05	0.14
188.35	0.20	0.05	0.15
188.45	0.55	0.05	0.50
188.55	1.18	0.05	1.13
188.65	2.00	0.05	1.95
188.75	2.98	0.05	2.93
188.85	3.87	0.05	3.81

Stage-Area-Storage for Pond B-2: Porous Pavement Within Tandem Spaces

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
186.85	3,564	0
186.95	3,564	143
187.05	3,564	285
187.15	3,564	428
187.25	3,564	570
187.35	3,564	713
187.45	3,564	855
187.55	3,564	998
187.65	3,564	1,140
187.75	3,564	1,283
187.85	3,564	1,426
187.95	3,564	1,568
188.05	3,564	1,711
188.15	3,564	1,853
188.25	3,564	1,996
188.35	3,564	2,138
188.45	3,564	2,281
188.55	3,564	2,424
188.65	3,564	2,566
188.75	3,564	2,709
188.85	3,564	2,851

Summary for Pond B-3: Infiltration Basin Along Sunset Road

Inflow Area = 52,620 sf, 14.98% Impervious, Inflow Depth = 5.07" for 100-Year event
 Inflow = 5.95 cfs @ 12.17 hrs, Volume= 22,218 cf
 Outflow = 2.75 cfs @ 12.35 hrs, Volume= 22,218 cf, Atten= 54%, Lag= 10.8 min
 Discarded = 0.06 cfs @ 12.35 hrs, Volume= 3,791 cf
 Primary = 2.69 cfs @ 12.35 hrs, Volume= 18,427 cf
 Routed to Link POI-1 : Proposed Drainage to Sunset Road

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs
 Peak Elev= 189.89' @ 12.35 hrs Surf.Area= 4,521 sf Storage= 6,767 cf

Plug-Flow detention time= 94.9 min calculated for 22,215 cf (100% of inflow)
 Center-of-Mass det. time= 95.0 min (912.6 - 817.6)

Volume	Invert	Avail.Storage	Storage Description		
#1	188.00'	7,255 cf	Custom Stage Data (Irregular) Listed below (Recalc)		
Elevation (feet)	Surf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)
188.00	2,670	308.6	0	0	2,670
189.00	3,625	227.5	3,135	3,135	6,140
190.00	4,635	346.3	4,120	7,255	11,572

Device	Routing	Invert	Outlet Devices
#1	Primary	187.50'	12.0" Round Culvert L= 325.0' Ke= 0.500 Inlet / Outlet Invert= 187.50' / 185.85' S= 0.0051 '/' Cc= 0.900 n= 0.013, Flow Area= 0.79 sf
#2	Device 1	188.25'	6.0" W x 3.0" H Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Device 1	188.80'	3.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#4	Device 1	189.60'	4.0' long x 1.0' breadth Broad-Crested Rectangular Weir Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 1.80 2.00 2.50 3.00 Coef. (English) 2.69 2.72 2.75 2.85 2.98 3.08 3.20 3.28 3.31 3.30 3.31 3.32
#5	Discarded	188.00'	0.500 in/hr Exfiltration over Surface area Conductivity to Groundwater Elevation = 180.10' Phase-In= 0.01'

Discarded OutFlow Max=0.06 cfs @ 12.35 hrs HW=189.89' (Free Discharge)

↑**5=Exfiltration** (Controls 0.06 cfs)

Primary OutFlow Max=2.69 cfs @ 12.35 hrs HW=189.89' TW=0.00' (Dynamic Tailwater)

↑**1=Culvert** (Passes 2.69 cfs of 3.21 cfs potential flow)

↑**2=Orifice/Grate** (Orifice Controls 0.74 cfs @ 5.93 fps)

↑**3=Orifice/Grate** (Orifice Controls 0.23 cfs @ 4.74 fps)

↑**4=Broad-Crested Rectangular Weir** (Weir Controls 1.72 cfs @ 1.46 fps)

Stage-Discharge for Pond B-3: Infiltration Basin Along Sunset Road

Elevation (feet)	Discharge (cfs)	Discarded (cfs)	Primary (cfs)
188.00	0.00	0.00	0.00
188.10	0.03	0.03	0.00
188.20	0.03	0.03	0.00
188.30	0.05	0.04	0.02
188.40	0.13	0.04	0.09
188.50	0.24	0.04	0.20
188.60	0.32	0.04	0.28
188.70	0.38	0.04	0.34
188.80	0.43	0.04	0.39
188.90	0.50	0.04	0.45
189.00	0.59	0.05	0.54
189.10	0.66	0.05	0.61
189.20	0.72	0.05	0.67
189.30	0.77	0.05	0.72
189.40	0.83	0.05	0.77
189.50	0.87	0.05	0.82
189.60	0.92	0.06	0.86
189.70	1.30	0.06	1.24
189.80	1.96	0.06	1.90
189.90	2.82	0.06	2.75
190.00	3.33	0.06	3.27

Stage-Area-Storage for Pond B-3: Infiltration Basin Along Sunset Road

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
188.00	2,670	0
188.10	2,759	271
188.20	2,849	552
188.30	2,941	841
188.40	3,035	1,140
188.50	3,129	1,448
188.60	3,226	1,766
188.70	3,323	2,093
188.80	3,422	2,431
188.90	3,523	2,778
189.00	3,625	3,135
189.10	3,720	3,503
189.20	3,817	3,879
189.30	3,915	4,266
189.40	4,014	4,663
189.50	4,115	5,069
189.60	4,216	5,485
189.70	4,319	5,912
189.80	4,423	6,349
189.90	4,528	6,797
190.00	4,635	7,255

Summary for Link POI-1: Proposed Drainage to Sunset Road

Inflow Area = 134,058 sf, 48.96% Impervious, Inflow Depth = 4.44" for 100-Year event
Inflow = 7.32 cfs @ 12.14 hrs, Volume= 49,566 cf
Primary = 7.32 cfs @ 12.14 hrs, Volume= 49,566 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.01 hrs

TABLE OF CONTENTS

100-Year Event

- 1 Subcat EX-1: Existing Drainage towards Sunset Road
- 2 Subcat EX-2: Existing Drainage towards Roome Avenue
- 3 Subcat EX-3: Existing Drainage towards Dewilde Drive
- 4 Subcat P-1A: Drainage to Infiltration Basin Along Sunset Road
- 5 Subcat P-1B: Drainage to Porous Pavement in Tandem Spaces
- 6 Subcat P-1C: Drainage to Infiltration Basin in Rear
- 7 Subcat P-1D: Undetained Flow to Sunset Road
- 8 Subcat P-2: Proposed Drainage to Roome Avenue
- 9 Subcat P-3: Proposed Drainage toward Dewilde Drive
- 10 Pond B-1: Infiltration Basin Along Sunset Road
- 13 Pond B-2: Porous Pavement Within Tandem Spaces
- 16 Pond B-3: Infiltration Basin Along Sunset Road
- 19 Link POI-1: Proposed Drainage to Sunset Road


APPENDIX D


DRAINAGE AREA MAPS

INVENTORY

SHEET 1 OF 2: EXISTING DRAINAGE AREA MAP

SHEET 2 OF 2: PROPOSED DRAINAGE AREA MAP



[illegible]

NOT APPROVED FOR CONSTRUCTION



Rutherford, NJ • New York, NY • Boston, MA
Princeton, NJ • Tampa, FL • Detroit, MI
www.stonefieldeng.com

Headquarters: 92 Park Avenue, Rutherford, NJ 07070
Phone 201.340.4468 • Fax 201.340.4472

DRAINAGE AREA MAPS

ONE SCHOOL GLOBAL

PROPOSED SCHOOL

**BLOCK 2104, LOT 21
60 SUNSET ROAD
TOWNSHIP OF PEQUANNOCK
MORRIS COUNTY, NEW JERSEY**

JAKE MODESTOW, P.E.
NEW JERSEY LICENSE No. 56119
LICENSED PROFESSIONAL ENGINEER



SCALE:	1" = 30'	PROJECT ID: RUT-220209
--------	----------	------------------------


TITLE:

**EXISTING DRAINAGE
AREA MAP**


DRAWING:

1 OF 2

Z:\RUTHERFORD\170322\17.220207 ONE SCHOOL GLOBAL - 40 SHARRET ROAD, PEQUANNOCK, NJ\CAD\170322\17.220207 ONE SCHOOL GLOBAL.dwg



SYMBOL	DESCRIPTION
---	PROPERTY LINE
---	EXISTING DRAINAGE AREA
---	EXISTING PERVIOUS AREA



STONEFIELD
engineering & design

Rutherford, NJ • New York, NY • Boston, MA
Princeton, NJ • Tampa, FL • Detroit, MI
www.stonefieldeng.com

Headquarters: 92 Park Avenue, Rutherford, NJ 07070
Phone 201.340.4468 • Fax 201.340.4472

ONE SCHOOL GLOBAL

PROPOSED SCHOOL

BLOCK 2104, LOT 21
60 SUNSET ROAD
TOWNSHIP OF PEQUANNOCK
MORRIS COUNTY, NEW JERSEY

JAKE MODESTOW, P.E.
NEW JERSEY LICENSE No. 56119
LICENSED PROFESSIONAL ENGINEER

STONEFIELD
engineering & design

SCALE: 1" = 30' PROJECT ID: RUT-220209

TITLE:
**PROPOSED DRAINAGE
AREA MAP**

DRAWING:

2 OF 2

NOT APPROVED FOR CONSTRUCTION

FOR CLIENT REVIEW	PK	BY	DATE	ISSUE	DESCRIPTION
	01		09/23/2022		